

Driving Climate Actions

Project Verification Report

V3.1 - 2020

www.globalcarboncouncil.com

© 2023 Global Carbon Council - All rights reserved

Project Verification Report

CONTENTS

cov	ER PAGE	5
1. F	PROJECT VERIFICATION REPORT	9
<u>SEC</u>	TION A.EXECUTIVE SUMMARY	9
<u>SEC</u>	TION B.PROJECT VERIFICATION TEAM, TECHNICAL REVIEWER AND APPROVER	<u>R 12</u>
<u>B.1.</u>	PROJECT VERIFICATION TEAM	<u>12</u>
<u>B.2.</u> REPO	TECHNICAL REVIEWER AND APPROVER OF THE PROJECT VERIFICATION ORT	<u>12</u>
SEC	TION C. <u>MEANS OF PROJECT VERIFICAT</u> 12	<u>ON</u>
<u>C.1.</u>	DESK/DOCUMENT REVIEW	12
<u>C.2.</u>	ON-SITE INSPECTION	12
<u>C.3.</u>	INTERVIEWS	<u>13</u>
<u>C.4.</u>	SAMPLING APPROACH	14
	CLARIFICATION REQUEST (CLS), CORRECTIVE ACTION REQUEST (CARS) AND WARD ACTION REQUEST (FARS) RAISED	<u>)</u> 14
SEC1	TION D.PROJECT VERIFICATION FINDINGS	15
<u>D.1.</u>	IDENTIFICATION AND ELIGIBILITY OF PROJECT TYPE	<u>15</u>
<u>D.2.</u>	GENERAL DESCRIPTION OF PROJECT ACTIVITY	<u>16</u>
	APPLICATION AND SELECTION OF METHODOLOGIES AND STANDARDIZED ELINES	18
	APPLICATION OF METHODOLOGY AND STANDARDIZED BASELINES CLARIFICATION ON APPLICABILITY OF METHODOLOGY, TOOL AND/OR STANDARDIZED BASEL 25	18 INE
D.3.4 D.3.5 D.3.6	 PROJECT BOUNDARY, SOURCES AND GHGS BASELINE SCENARIO DEMONSTRATION OF ADDITIONALITY ESTIMATION OF EMISSION REDUCTIONS OR NET ANTHROPOGENIC REMOVAL MONITORING PLAN 	25 25 26 32 33

<u>D.4.</u>	START DATE, CREDITING PERIOD AND DURATION	38
<u>D.5.</u>	ENVIRONMENTAL IMPACTS	38
<u>D.6.</u>	LOCAL STAKEHOLDER CONSULTATION	39
<u>D.7.</u>	APPROVAL AND AUTHORIZATION- HOST COUNTRY CLEARANCE	39
<u>D.8.</u>	PROJECT OWNER- IDENTIFICATION AND COMMUNICATION	39
<u>D.9.</u>	GLOBAL STAKEHOLDER CONSULTATION	40
<u>D.10</u> .	ENVIRONMENTAL SAFEGUARDS (E+)	40
<u>D.11.</u>	SOCIAL SAFEGUARDS (S+)	41
<u>D.12</u> .	SUSTAINABLE DEVELOPMENT GOALS (SDG+)	42
<u>D.13</u> .	AUTHORIZATION ON DOUBLE COUNTING FROM HOST COUNTRY (FOR COP	<u>(SIA)</u>
<u>D.14</u> .	CORSIA ELIGIBILITY (C+)	44
SEC	<u>INTERNAL QUALITY CON</u>	<u>TROL</u>
<u>SEC</u>	TION F.PROJECT VERIFICATION OPINION	44
Appe Appe	ndix 1. Abbreviations ndix 2. Competence of team members and technical reviewers ndix 3. Document reviewed or referenced ndix 4. Clarification request, corrective action request and forward action request	46 48 51 52

	COVER PAGE					
Project Verification Report Form (PVR)						
Complete this form in accordance with	Complete this form in accordance with the instructions.					
	BASIC INFORMATION					
Name of approved GCC Project Verifier / Reference No. (also provide weblink of approved	Carbon Check (India) Private Limited. / GCCV004/00 http://globalcarboncouncil.com/wp- content/uploads/2021/10/carbon-check-india-private-limited-					
GCC Certificate) Type of Accreditation	ccipl.pdf Individual Track1 CDM Accreditation: E-0052 https://cdm.unfccc.int/DOE/list/DOE.html?entityCode=E-0052 Valid until 01/06/2024 ISO 14065 Accreditation: GH004 https://nabcb.qci.org.in//accreditation/ghg/ghg004.php Valid from 28/06/2021 until 27/06/2024					
Approved GCC Scopes and GHG Sectoral scopes for Project Verification	 GCC Scopes: Environmental No-harm (E+) Green House Gas (GHG) Environmental No-net harm (E+) Social No-harm (S+) Sustainable Development Goals (SDG+) GHG Sectoral Scope: 1. Energy (renewable/non-renewable sources) 					
Validity of GCC approval of Verifier	08/03/2023 to 31/05/2024					
Title, completion date, and Version number of the PSF to which this report applies	Wind Power Project Activity in MP, India Version number 3.0, dated 04/09/2023					
Title of the project activity	Wind Power Project Activity in MP, India					
Project submission reference no. (as provided by GCC Program during GSC)	S00340					
Eligible GCC Project Type ² as per the Project Standard	 ☑ Type A: ☑ Type A1 					

¹ **Note:** GCC Verifier under Individual tack is not eligible to conduct verifications for the GCC project that intends to supply carbon credits (ACCs) for CORSIA requirements.

² Project Types defined in Project Standard and Program Definitions on GCC website.

(Tick applicable project type)	🛛 Туре А2					
	Type B – De-registered CDM Projects:					
	Type B1	0				
	$\Box Type^{3} B2$					
Date of completion of Local stakeholder consultation	28/05/2022					
Date of completion and period of	08/09/2022 – 22/09/2	022				
Global stakeholder consultation. Have the GSC comments been	No comments were r	received.				
verified. Provide web-link.	https://www.globalca consultation-4/	rboncouncil.com/glob	al-stakeholders-			
Name of Entity requesting verification service	Roha Dyechem Private Limited					
(can be Project Owners themselves or any Entity having authorization of Project Owners)	Arkas Energy LLP					
Contact details of the	On behalf of Roha Dyechem Pvt. Ltd and Arkas Energy LLP					
representative of the Entity, requesting verification service	Name: Meenkshi Jair	ı				
(Focal Point assigned for all	Designation: Managir	-				
communications)	Email: meenakshi@p					
	·	ative: Positive Climate	e Care Private Limited.			
Country where project is located	India		1			
GPS coordinates of the Project site(s)	WTG	Latitude	Longitude			
510(5)	NPY P-73	25°19'49.86'' N (24.330718°N)	75°31'59.34" E (75.532922°E)			
	NPY P-72	24°20'5.56" N (24.3349°N)	75°32'7.00" E (75.5353° E)			
	NPY P3-88	24.15816° N (24.15816° N)	75°27'18.90" E (75.45525° E)			
	NPY P-42 24°11'35.27" N (24.193131° N) 75°27'1.24" E (75.450344° E)					
	NPY P3-87 24°10'0.01" N 75°27'35.31" E (24.16667° N) (75.45981° E)					
Applied methodologies (approved methodologies of GCC or CDM can be used)	AMS-I.D.: Grid connected renewable electricity generation Version 18.0					

³ GCC Project Verifier shall conduct Project Verification for all project types except B₂.

GHG Sectoral scopes linked to the applied methodologies	Scope 1 - Energy (renewable/non-renewable source)
Project Verification Criteria: Mandatory requirements to be assessed	 ISO 14064-2, ISO 14064-3 GCC Rules and Requirements Applicable Approved Methodology Applicable Legal requirements /rules of host country National Sustainable Development Criteria (if any) Eligibility of the Project Type Start date of the Project activity Meet applicability conditions in the applied methodology Credible Baseline Additionality Emission Reduction calculations Monitoring Plan No GHG Double Counting Local Stakeholder Consultation Process Global Stakeholder Consultation Process United Nations Sustainable Development Goals (Goal No 13- Climate Change) Others (please mention below)
Project Verification Criteria: Optional requirements to be assessed	 Environmental Safeguards Standard and do-no-harm criteria Social Safeguards Standard do-no-harm criteria United Nations Sustainable Development Goals (in additional to SDG 13) CORSIA requirements
Project Verifier's Confirmation: The GCC Project Verifier has verified the GCC project activity and therefore confirms the following:	 he GCC Project Verifier Carbon Check (India) Private Limited, certifies the following with respect to the GCC Project Activity Wind Power Project Activity in MP, India. The Project Owner has correctly described the Project Activity in the Project Submission Form (version 1.0, dated 16/06/2022) including the applicability of the approved methodology AMS-I.D.: Grid connected renewable electricity generation Version 18.0 and meets the methodology applicability conditions and is expected to achieve the forecasted real and additional GHG emission reductions, complies with the monitoring methodology, has appropriately conducted local and global stakeholder consultation processes and has calculated emission reductions estimates correctly and conservatively. The Project Activity is likely to generate GHG emission reductions amounting to the estimated 149,250 tCO_{2e}, throughout

Name of the authorised personnel of GCC Project Verifier and his/her signature with date	Vikash Kumar Singh, Compliance Officer/Executive Director
Project Verification Report, reference number and date of approval	Report: CCIPL1730 Version 03.0 Dated 07/09/2023
	additional to the reductions that are likely to occur in absence of the Project Activity and complies with all applicable GCC rules, including ISO 14064-2 and ISO 14064-3.
	the 10 years of crediting period as indicated in the PSF, which are

⁴ SDG Certification labels: Bronze label (1 star): by achieving 2 out of 17 SDGs; Silver label (2 star): by achieving 3 out of 17 SDGs; Gold label (3 star): by achieving 4 out of 17 SDGs; Platinum label (4 star): by achieving 5 out of 17 SDGs; and Diamond label (5 star): by achieving more than 5 out of 17 SDGs.

⁵ "GCC Rules" are defined in Project Definitions and refers to the rules and requirements set out by the GCC program related to GHG emission reductions and its voluntary certification labels and are available on the GCC Program's public website: <u>https://www.globalcarboncouncil.com/resource-centre.html</u>

1. PROJECT VERIFICATION REPORT

Section A. Executive summary

Roha Dyechem Private Limited has appointed the GCC Project Verifier, Carbon Check (India) Private Ltd., to perform an independent project verification/ of the Project "Wind Power Project activity in MP, India " (hereafter referred to as "project"). This report summarizes the findings of project verification of the project, performed on the basis of GCC rules and requirements as well as criteria given to provide for consistent project operations, monitoring and reporting. This report contains the findings and resolutions from the project verification and a verification opinion. Roha Dyechem Private Limited and Arkas Energy LLP have constructed the Wind Power Project Activity in MP, India. The aim of the project is to generate clean energy and feed it to the Indian national grid. The location and the GPS coordinates of the project site is as follows.

Project Promoters	Capacity (MW)	WTG Location No.	Location	Commissioning Date
	2	NPY P-72	Village - Dethali Bujurg, Tehsil- Garoth, District	
Roha Dyechem Pvt. Ltd.	2	NPY P-73	Mandsaur	
(capacity 6 MW)	2	NPY P3-88	Village – Garada, Tehsil - Shamgarh, District Mandsaur	10/06/2016
Arkas Energy	2	NPY P-42	Village-Chandwasa & Bhatuni Tehsil -	
LLP (capacity 4MW)	2	NPY P3-87	Shamgarh, District Mandsaur	

The bundled project includes 5 units of windmills each with a capacity of 2 MW, totalling 10 MW. The estimated annual electricity generation capacity of the project is 16,031 MWh and the project is expected to reduce CO2 emissions by 14,925 tCO2e per year and a total reduction of 149,250 tCO2e throughout the crediting period of 10 years.

The date of commissioning of all the 5 WTGs were on 10/06/2016.

The project also contributes to Environmental No-net-harm Label (E+), Social No-net-harm Label (S+),

CORSIA requirements (C+) and 7 United Nations Sustainable Development Goals (SDG+) i.e., SDG 3,4,6,7,8,13, and 15.

The purpose of the project verification is to have a thorough and independent assessment of the proposed Project Activity against the applicable GCC rules and requirements, including those specified in the Project Standard, applied methodology/methodological tools and any other requirements, in particular, the project's baseline, monitoring plan and the host Party criteria. These are verified to confirm that the project design, as documented, is sound and reasonable and meets the identified criteria. Verification requirement for all GCC projects activity is necessary to provide assurance to stakeholders of the quality of the Project and its intended generation of Approved Carbon Credits (ACCs).

Scope of project verification

The project verification scope is defined as the independent and objective review of the project submission form. The PSF /01/ is reviewed against the relevant criteria and decisions by the GCC, including the CDM approved baseline and monitoring methodology and tools. The verification team has, based on the recommendations in the GCC Project Standard, Version

3.1/B01-A/ and Project Verification Standard Version 3.1/B01-B/ employed a rule-based approach, focusing on the identification of significant risks for project implementation and the generation of ACCs.

The verification is not meant to provide any consulting towards the project (owner)s. However, stated requests for clarifications and/or corrective actions may have provided input for improvement of the program design.

While carrying out the verification, CCIPL determines if the PSF complies with the requirements of the applicability conditions of the selected methodology/B02/, guidance issued by the GCC and also assess the claims and assumptions made in the PSF/01/ without limitation on the information provided by the project owner.

Verification Process

Strategic risk Analysis and delineation of the verification plan:

CCIPL employed the following validation (termed as "Project Verification" as per GCC) process:

- 1. Conflict of interest review at the time of contract review;
- 2. Selection of Audit Team at the time of contract review;
- 3. Kick-off meeting with the client;
- 4. Review of the draft PSF listed on GCC website for public consultation;
- 5. Development of the verification plan.
- 6. Desktop review and evaluation of emission reduction calculations;
- 7. Follow-up interaction with the client; and final statement and report development.

The validation process has utilized to gain an understanding of the:

- Project's design, GHG emission sources and reductions,
- Baseline determination and additionality,
- GHG monitoring plan,
- Environmental & Social impacts,
- Stakeholder's consultation,
- SD indicators integrated with the project and

• Verify the collection and handling of data, the calculations that lead to the results, and the means for reporting the associated data and results.

Development of the Project Verification Plan:

The Audit Team formally documented its verification plan:

The Project Verification plan was developed based on discussion of key elements of the verification process during the kick-off meeting and as per the criteria of engagement. Client had the opportunity to comment on key elements of this plan for verification. Based on items discussed above and agreed upon with the client in the signed contract, the plan identified the CCIPL audit team members based on following:

- Project level of assurance (which is reasonable as per GCC requirements),
- Materiality threshold and
- Standards of evaluation and reporting for the verification.

It also provides an outline of the Project Verification process and established project deliverables. The project verification consists of the following four phases:

I. A desk review of the project submission form.

• A review of the data and information;

• Cross checks between information provided in the PSF /01/ and information from sources with all necessary means without limitations to the information provided by the project owner;

II. Follow-up interviews with project stakeholders

• Interviews with relevant stakeholders in host country with personnel having knowledge with the project development;

• Cross checking between information provided by interviewed personnel with all necessary means without limitations to the information provided by the project owner;

III. Reference to available information relating to projects or technologies similar projects under verification and review based on the approved methodology /B02/ being applied of the appropriateness of formulae and accuracy of calculations.

IV. The resolution of outstanding issues and the issuance of the final verification report and opinion.

The Verification team confirms the contractual relationship signed between the GCC Project Verifier, CCIPL and the Project Owner. The team assigned to the verification meets the CCIPL's internal procedures including the GCC requirements for the team composition and competence. The verification team has conducted a thorough contract review as per GCC and CCIPL's procedures and requirements.

The report is based on the assessment of the PSF /01/ undertaken through stakeholder consultations, application of standard auditing techniques including but not limited to document reviews and stakeholder interviews, review of the applicable/applied methodology and their underlying formulae and calculations.

This report contains the findings (which need to be resolved by the PO) from the verification and a verification opinion on the proposed Project will be provided once all the raised findings are successfully resolved by the project owner to confirm the program design in the documents is sound and reasonable and meets the stated requirements and identified criteria.

Conclusion

The CDM baseline and monitoring methodology AMS-I.D.: Grid connected renewable electricity generation, Version 18.0/B02/ has been applied to the project.

Carbon Check (India) Private Ltd. is able to conclude the verification with a positive opinion that the GCC Project Activity "Wind Power Project Activity in MP, India" as described in the PSF (Version 3.0, dated 04/09/2023) /01/, meets all applicable GCC rules and requirements, including those specified in the Project Standard /B01-A/, applied CDM methodology, tools and guidelines from GCC (please refer to Appendix 4 for the details of the raised findings). Carbon Check (India) Private Ltd. therefore will be able to recommend the project to the GCC for registration subject to closure of all the raised findings (please refer to Appendix 4 for the details of the raised findings).

Section B. Project Verification team, technical reviewer and approver

B.1. Project Verification team

No.	Role		Last name	First name	Affiliation		nvolve	ment i	n
		Type of resource			(e.g. name of central or other office of GCC Project Verifier or outsourced entity)	Desk/document review	On-site inspection	Interviews	Project Verification findings
1.	Team Leader /technical Expert	İR	Choudhary	Aparna	CCIPL	Х	Х	Х	Х
2.	Assessor	IR	ΚV	Kiran	CCIPL	Х	Х	Х	Х
3.	Financial/ Other Expert	IR	Kumar	Hetal	CCIPL	Х			Х

B.2. Technical reviewer and approver of the Project Verification report

No.	Role	Type of resource	Last name	First name	Affiliation (e.g. name of central or other office of GCC Project Verifier or
					outsourced entity)
1.	Technical reviewer	IR	С	Indumathi	CCIPL
	Approver	IR	Singh	Vikash Kumar	CCIPL

Section C. Means of Project Verification

C.1. Desk/document review

The verification was performed primarily as a document review of the initial PSF/01-a/ and revised/final PSF /01-b/. The verification of information provided in the PSF was performed using the source of information provided by the project owner. Additionally, the cross checks were performed for information provided in the PSF using information from sources other than the verification sources, the verification team's sectoral or local expertise and, if necessary, independent background investigations.

List of all documents reviewed or referenced during the project verification is provided in Appendix-3.

C.2. On-site inspection

	Duration of on-site inspection: 03/06/2023 – 03/06/2023					
No.	Activity performed on-site	Site location	Date	Team member		

1.	Opening Meeting and brief project			
	description by the PO			
2.	Project implementation and legal			
	requirements			
3.	Discussion on Monitoring plan, monitoring			
	process, operational and management			Aparna
	structure for monitoring, and responsibility			Choudhary
	and institutional arrangement for data			(Team
	collection and archiving. Implementation	INOX office, Village-	03/06/2023	leader/Technic
	of monitoring plan as per the Project	Bhaguniya, Tehsil-		al expert)
	submission Form (PSF).	Sharmgarh, District-		Kiran K V
4.	Discussion on Environmental Impacts,	Mandsaur, MP, india		(Assessor)
	Social Impacts ,United Nations			
	Sustainable Development Goals , and			
	CORSIA requirements			
5.	Discussion on Baseline determination,			
	Methodological applicability, Additionality			
	requirement, Emission reduction			
	calculation, Local Stakeholder			
6	Consultation			
6. 7.	Interview with local stakeholders.	1. Delmu Cubetetier ard		
1.	Physical site visit (to check project implementation and operation)	1. Dalmu Substation and		
		connected WTGs, Village Delti Bujurg,		
		Tehsil- Garoth, District-		Aparna
		Mandsaur, MP, India.		Choudhary
			03/06/2023	(Team
		2. Chandwasa	00,00,2020	leader/Technic
		substation and		al expert)
		connected WTGs,		Kiran K V
		Village- Bhaguniya,		(Assessor)
		Tehsil- Garoth, District-		(
		mandsaur, MP, India		
8.	Closing meeting	, ,		Aparna
		INOX office, Village-		Choudhary
		Bhaguniya, Tehsil-		(Team
		Sharmgarh, District-	03/06/2023	leader/Technic
		Mandsaur, MP, india		al expert)
				Kiran K V
				(Assessor)

C.3. Interviews

No.		Interview		Date	Subject	Team member
	Last name	First name	Affiliation		-	
1.	Jain	Meenakshi	Positive Climate Care Pvt. Ltd	03/06/2023	Implementation of monitoring plan as per PSF, Baseline determination, Additionality requirement, Emission reduction calculation, Legal requirements.	Aparna Choudhary
2.	Bhutada	Shrikisan	Roha Dyechem Pvt Ltd	03/06/2023	Project	(Team leader/Technical expert)
3.	Sharma	Rajesh	Roha Dyechem Pvt Ltd.	03/06/2023	implementation, Operation and management	Kiran K V (Assessor)
4.	Lal	Рорро	Inox Green Energy Pvt Ltd	03/06/2023	structure, Implementation of monitoring	
5.	Yadav	Jitendra Prasad	Inox Green Energy Pvt Ltd	03/06/2023	plan, Data collection and archieving, E+,	
6.	М	Manith	Inox Green Energy Pvt Ltd	03/06/2023	S+ and SDGs	
7.	Bali	Baliram	Inox Green Energy Pvt Ltd/ LSC attendee	03/06/2023	Local stakeholder consultation discussions,	
8.		Sonu	LSC Attendee	03/06/2023	grievances,	

C.4. Sampling approach

>> NA

C.5. Clarification request (CLs), corrective action request (CARs) and forward action request (FARs) raised

Areas of Project Verification findings	Applicable to Project Types	No. of CL	No. of CAR	No. of FAR
Green House Ga	is (GHG)			
Identification and Eligibility of project type	A ₁ , A ₂ , B ₁ , B ₂			
General description of project activity	A ₁ , A ₂ , B ₁ , B ₂	CL03, CL07, CL08	CAR01	
Application and selection of methodologies and standardized baselines	A ₁ , A ₂ , B ₁ , B ₂			

 Application of methodologies and standardized baselines 	A ₁ , A ₂ , B ₁ , B ₂	CL01	CAR02	
 Deviation from methodology and/or methodological tool 	A ₁ , A ₂ , B ₁ , B ₂			
 Clarification on applicability of methodology, tool and/or standardized baseline 	A ₁ , A ₂ , B ₁ , B ₂			
 Project boundary, sources and GHGs 	A1, A2, B1, B2			
- Baseline scenario	A ₁ , A ₂ , B ₁ , B ₂		CAR03, CAR04	
 Demonstration of additionality including the Legal Requirements test 	A ₁ , A ₂ , B ₁ , B ₂	CL05, CL06, CL09, CL16	CAR05, CAR06, CAR07	
 Estimation of emission reductions or net anthropogenic removals 	A ₁ , A ₂ , B ₁ , B ₂			
- Monitoring plan	A ₁ , A ₂ , B ₁ , B ₂	CL02, CL04, CL10	CAR08, CAR09	
Start date, crediting period and duration	A1, A2, B1, B2	CL 21		
Environmental impacts	A1, A2, B1, B2			
Local stakeholder consultation	A1, A2, B1	CL 20		
Approval & Authorization- Host Country Clearance	A1, A2, B1, B2			FAR 01
Project Owner- Identification and communication	A1, A2, B1, B2	CL11		
Global stakeholder consultation	A1, A2, B1			
Others (please specify)	A1, A2, B1, B2			
VOLUNTARY CERTIFIC	ATION LABELS			-
Environmental Safeguards (E ⁺)	A ₁ , A ₂ , B ₁	CL12. CL13 CL 17 CL 18		
Social Safeguards (S ⁺)	A1, A2, B1	CL14, CL15		
Sustainable development Goals (SDG ⁺)	A ₁ , A ₂ , B ₁	CL 19		
Authorization on Double Counting from Host Country (only for CORSIA)	A ₁ , A ₂ , B ₁			
CORSIA Eligibility (C ⁺)				
Total		21	09	01

Section D. Project Verification findings

D.1. Identification and eligibility of project type

Means of Project Verification	Desk Review and on-site inspection
Findings	No findings
Conclusion	The Verification team reviewed the PSF /01/ and confirms that the Project Owner determines the type of proposed GCC project activity as Type A2. Such project activity shall have the start date of operations after 1 January 2016. These projects are required to make initial submission to GCC program, for uploading for global stakeholder consultation, prior to 5 July 2022.
	This bundled project activity is categorized as Type A2 due to its commencement of operations on 10 June 2016, falling within the timeframe of 1 January 2016 to 5 July 2022. Moreover, VVB has crosschecked that the bundled project fulfils the CORSIA requirements as mentioned in section D.1 of the PSF. VVB confirms that the project

is not submitted to any other GHG program as checked in registries of all other GHG programs by the VVB. The sub-type 1 under type A2 has been defined for the project activity. This type includes existing operational projects, not submitted to any GHG Program, which have started operations after 1 January 2016. Such project types shall make the initial submission to GCC Program prior to 5 July 2022
The proposed project activity has started its operations on 10/06/2016 (date of commissioning 05/, its start date of crediting period is 01/08/2016. The initial submission to the GCC program has been done on 17/06/2022 and the GSC period was from 08/09/2022 to 22/09/2022. This complies with the requirement of §11 of the GCC Project Standard (version 03.1) /B01-A/ and § 25 (b) of GCC Project Verification Standard (version 03.1) /B01-B/ and § 3(c) of GCC clarification no.1 (version 1.1).
The bundled project is eligible against (i) the GCC Project standard version 3.1, specifically with respect to Section 5.1" Common Eligibility Criteria for All Project Types" vide paragraph 14 & 15 and Section 5.2 "Specific Eligibility Criteria for Type A Projects" vide paragraph 16, and (ii) GCC Clarification No. 01, v1.3 paragraph 29, the same has been explained in the PSF under section B.2 and cross checked by the VVB documents /5/,/4/,/12/ and by checking the statutory authorities.

D.2. General description of project activity

Means of Project Verification	Desk Review and on-site inspection
Findings	CL03, CL07, CL08, CAR01 has been raised
	CL03, CL07, CL08, CAR01 has been raised The description of the project activity contained in the PSF /1/ can be considered transparent, detailed and provides a clear overview of the project (subject to revision in the PSF against the raised findings. please refer to Appendix 4 for further details of the findings). Roha Dyechem Pvt Ltd and Arkas Energy LLP developed the proposed activity which involves installation of Wind turbine generators to generate clean electricity and feed to the Indian national grid. A total of 5 WTGs each with a capacity of 2 MW totalling 10 MW has been installed as part of this bundled project activity. The project verification team has confirmed the same by cross verifying the commissioning report /5/, PPAs /4/ and physical verification of project site /17/ Since, the wind energy is clean energy, the project activity does not involve any fossil fuel firing and hence no greenhouse gases are involved in the project activity. The power generation from the project activity replaces the equal amount of power which otherwise would have been supplied from the fossil fuel dominated grid Estimated electricity generation and corresponding annual estimated emission reduction values are 16,031 MWh and 14,925 tCO ₂ e per annum respectively.
	given below.

Project Promoters	Capacity (MW)	WTG Location No.	Location
	2	NPY P-72	Village - Dethali
Roha Dyechem Pvt. Ltd. (capacity 6 MW)	2	NPY P-73	Bujurg, Tehsil- Garoth, District Mandsaur
	2	NPY P3-88	Village – Garada, Tehsil - Shamgarh, District Mandsaur
	2	NPY P-42	Village-Chandwasa
Arkas Energy LLP (capacity 4MW)	2	NPY P3-87	& Bhatuni Tehsil - Shamgarh, District Mandsaur

The location of the project activity has been cross verified by the verification team with the use of remote sensing software (Google earth) and confirm that the location given by the Project Owners is appropriate

The owners of the Bundled project activities are Roha Dyechem Pvt Ltd and Arkas Energy LLP. The letter of Authorization submitted to VVB/16/ is duly signed by both the PO.

The technology used wind turbine generator model WT 2000 DF manufactured by Inox wind energy limited. 5 WTGs are employed to produce the total project capacity of 10 MW power /4/ /5/. The technical specification of the WTGs is confirmed from the purchase order document /7/ and onsite visit/17/. The project activity is the green field activity, as confirmed during the site visit and discussion with the project owner, there was no renewable energy operating prior to the implementation of the project activity. The same has also confirmed from the purchase order issued to the technology provider /7/. The project has been connected to the grid and started its first delivery to the grid on 10/06/2016 and the project verification team confirms the same from commissioning report /5/. The baseline scenario is that the electricity delivered to the grid by the project activity would be generated by the operation of grid-connected power plants and by the addition of new generation sources into the grid. The same complies with the applied methodology /B02/.

ACCs issued will be used to create additional revenue stream for the investment and for reducing the project financial risks and thus enabling the sustainability of the project.

During the 25 years lifetime/4/, the project is expected to supply an average of 16,031 MWh electricity to India national grid per year. As stated in the PSF /1/, the project activity also voluntarily contributes to Environmental No-net-harm Label (E+), Social No-net-harm Label (S+) and 7 United Nations Sustainable Development Goals (SDG+).

As per the PSF /1/, start date of the Project Activity is 10/06/2016 (commissioning date) /5/. The same is in accordance with requirements of §38 of Project Standard (version 03.1) /B01-A/.

Crediting period is a fixed crediting period for the Project Activity, from 01/08/2016 to 31/07/2026 i.e., of 10 years. The generation was not stabilized until August 2016 despite the commissioning of all five machines on June 10, 2016, hence PO decided

a crediting period beginning in August 2016. This is cross checked by PSF /1/ and conforms the requirement of §39 and §40 of Project Standard Version 03.1 /B01-A/.
CCIPL is able to confirm that the description of the proposed Project Activity in the PSF is accurate and complete and it provides an understanding of the Project Activity.

D.3. Application and selection of methodologies and standardized baselines

D.3.1 Application of methodology and standardized baselines

Means of Project Verification	Desk Review and on-site inspection	n	
Findings	CL01 and CAR02 has been raised		
Conclusion	The CDM methodology applied is greenfield renewable energy power the methodology could be confirm representatives, physical site visit The applied methodology is correct on the UNFCCC website. The a methodology /B02/ is valid at the tir consultation. All applicability criter table:	AMS-I.D, version 18.0 er generation using wind ed by means of interview and document review. ctly quoted and is identic applied version of the me of submission of the F	d energy. Applicability of ws with the project owner al to the version available baseline and monitoring PSF for global stakeholder
	Applicability criteria of the methodology (AMS-I.D, version 18)	Justification in the PSF	DOE assessment
	 This methodology comprises renewable energy generation units, such as photovoltaic, hydro, tidal/wave, wind, geothermal and renewable biomass: (a) Supplying electricity to a national or a regional grid; or (b) Supplying electricity to an identified consumer facility via national/regional grid through a contractual arrangement such as wheeling. 	The bundled project activity involves the installation of a green-field wind project for renewable electricity generation. It would supply electricity to the Indian grid that is primarily dominated with fossil fuel fired generating units therefore it meets this condition.	The bundled proposed activity is a, Greenfield project, which involves the installation of a new grid- connected renewable power generation facility (i.e. 10 MW of wind power plant). CCPIL project verification team confirmed the same from the purchase order issued to the technology provider /7/, power purchase agreement signed /4/, and the commissioning certificates /5/. Hence the methodology is applicable to the proposed project activity.
	2. This methodology is applicable to project activities that (a) install a new power plant at a site where there was no renewable energy power plant	The bundled project activity is the installation of a new wind power plant i.e. Greenfield plant.	There is no capacity addition, retrofitting or replacements in the proposed bundled project activity. The

		T
operating prior to the implementation of the project activity (Greenfield plant); (b)involve a capacity addition; ⁶ (c)involve a retrofit of (an) existing plant(s); or (d)involve a replacement ⁷ of (an) existing plant(s).	Hence, this applicability criterion is satisfied.	proposed activity is a, Greenfield project, which involves the installation of a new grid- connected renewable power generation facility 10 MW of wind power plant). CCPIL project verification team confirmed the same during the onsite visit /17/. Hence this condition is not applicable to the proposed bundled project activity.
 4. Hydro power plants with reservoirs⁸ that satisfy at least one of the following conditions are eligible to apply this methodology: The project activity is implemented in an existing reservoir with no change in the volume of reservoir. The project activity is implemented in an existing reservoir⁹, where the volume of reservoir⁹, where the volume of reservoir is increased and the power density of the project activity, as per definitions given in the Project Emissions section, is greater than 4 W/m²; 	The bundled project activity is a wind power project. Hence this criterion is not applicable to the project activity.	The proposed bundled project activity is not a hydro power project. The proposed activity is a, Greenfield project, which involves the installation of a new grid- connected renewable power generation facility (10 MW of wind power plant). CCPIL project verification team confirmed the same during the onsite visit /17/. Hence this condition is not applicable to the proposed bundled project activity.
new reservoirs and the power density of the power plant, as per definitions given in the Project Emissions section, is greater than 4 W/m ² 5. If the new unit has both renewable and non-renewable components (e.g., a wind/diesel unit), the eligibility limit of 15	The bundled project has a total capacity of 10 MW. The unit has no non-	The proposed bundled project activity is not a integrated hydro power project. The proposed
MW for a small-scale CDM	renewable	bundled project activity

⁹ A reservoir is to be considered as an "existing reservoir" if it has been in operation for at least three years before the implementation of the project activity.

project activity applies only to the renewable component. If the new unit co-fires fossil fuel, ¹⁰ the capacity of the entire unit shall not exceed the limit of 15 MW.	components or provision for future addition of a co-fired fossil fuel system. Thus, the project activity meets the applicability condition.	is a, Greenfield project, which involves the installation of a new grid- connected renewable power generation facility (i.e. 10 MW of wind power plant). CCPIL project verification team confirmed the same during the onsite visit /17/. Hence this condition is not applicable to the proposed project activity.
6. Combined heat and power (co-generation) systems are not eligible under this category.	The bundled project activity does not involve cogeneration and hence it satisfies the applicability criteria.	The proposed bundled project activity is not fuel switch project from fossil fuels to renewable energy sources, biomass fired power plants and the hydro power plant that result in new reservoir. The proposed activity is a, Greenfield project, which involves the installation of a new grid- connected renewable power generation facility (i.e. 10 MW of wind power plant). CCPIL project verification team confirmed the same during the onsite visit /17/. Hence this condition is not applicable to the proposed project activity.
7. In the case of project activities that involve the addition of renewable energy generation units at an existing renewable power generation facility, the added capacity of the units added by the project should be lower than 15 MW and should be physically	This condition is not applicable to the bundled project activity as it is a new grid connected renewable wind project activity and does involve the addition of renewable	The proposed bundled project activity does not involve any retrofits, replacements or capacity addition. The proposed activity is a, Greenfield project, which involves the installation of a new

¹⁰ A co-fired system uses both fossil and renewable fuels, for example the simultaneous combustion of both biomass residues and fossil fuels in a single boiler. Fossil fuel may be used during a period of time when the biomass is not available and due justifications are provided.

		· · · · ·
distinct ¹¹ from the existing units.	units at an existing renewable power generation facility.	renewable power generation facility (i.e. 10 MW of wind power plant). CCPIL project verification team confirmed the same during the onsite visit /17/. Hence this condition is not applicable to the proposed project activity.
8. In the case of retrofit or replacement, to qualify as a small-scale project, the total output of the modified or retrofitted unit shall not exceed the limit of 15 MW	This condition is not applicable to the bundled project activity as it is not a modification/ retrofit measure in an existing power plant.	The proposed bundled project activity does not involve any retrofits, replacements or capacity addition. The proposed activity is a, Greenfield project, which involves the installation of a new grid- connected renewable power generation facility (i.e. 10 MW of wind power plant). CCPIL project verification team confirmed the same during the onsite visit /17/. Hence this condition is not applicable to the proposed project activity.
In the case of landfill gas, waste gas, wastewater treatment and agro-industries projects, recovered methane emissions are eligible under a relevant Type III category. If the recovered methane is used for electricity generation for supply to a grid then the baseline for the electricity component shall be in accordance with procedure prescribed under this methodology. If the recovered methane is used for heat generation or cogeneration other applicable Type-I methodologies such as "AMSI.	The bundled project activity is the installation of a new grid connected 10 MW renewable wind power project. Hence this criterion is not applicable.	The proposed bundled project activity does not involve any Landfill

¹¹ Physically distinct units are those that are capable of generating electricity without the operation of existing units, and that do not directly affect the mechanical, thermal, or electrical characteristics of the existing facility. For example, the addition of a steam turbine to an existing combustion turbine to create a combined cycle unit would not be considered "physically distinct".

C.: Thermal energy production		during the onsite visit
with or without electricity" shall		/17/. Hence this
be explored.		condition is not applicable to the
		applicable to the proposed project
		activity.
In case biomass is sourced from	The bundled project	The proposed bundled
dedicated	activity is the	project activity does not
plantations, the applicability	installation of a new	involve biomass as a
criteria in the tool	grid connected 10	source. The proposed
"Project emissions from	MW renewable wind	activity is a Greenfield
cultivation of biomass"	power	project, which involves the installation of a new
shall apply.	project. Hence this criterion is not	grid- connected
	applicable.	renewable power
		generation facility (i.e.
		10 MW of wind power
		plant). CCPIL project
		verification team
		confirmed the same
		during the onsite visit /17/. Hence this
		/17/. Hence this condition is not
		applicable to the
		proposed project
		activity.
in Section 4 of 'Clarification No. 1 been cross verified by the VVB including technical specification of visit. Applicability conditions of "Tool to	by checking all the do all equipment used on	cuments of the projects site physically during site
system"		
Applicability criteria of the tool 7, Version 7.0	Justification in the PSF	DOE assessment
The tool lists the following	Since this project	The project activity
applicability criteria:	activity is grid	involved the
	connected and the	construction and
(a) This tool may be applied to	emission factor is	operation of 10 MW of
estimate the OM, BM and/or CM when calculating baseline	estimated using this tool (under	wind power plant in India. The electricity
emissions for a project activity	section B.4) for	thus generated is being
that substitutes grid electricity	calculating of the	sold to Indian national
that is where a project activity	baseline emission.	grid. In the absence of
supplies electricity to a grid or a	Hence this tool is	the project activity, the
project activity that results in	applicable.	same amount of
savings of electricity that would		electricity (grid
have been provided by the grid		electricity) would be
have been provided by the grid (e.g. demand-side energy		electricity) would be generated in Indian
have been provided by the grid		electricity) would be

-	ſ	
		margin calculation applies to the Indian national grid.
Under this tool, the emission factor for the project electricity system can be calculated either for grid power plants only or, as	Central Electricity Authority of India published a database named "CO2	PP has used the emission factor from Central Electricity Authority of India
an option, can include off-grid power plants. In the latter case, the conditions specified in "Appendix 2: Procedures related to off-grid power generation" should be met.	Baseline database for the Indian Power Sector" in which it follows this Tool to demonstrate step wise approach for the	published a database named "CO2 Baseline database for the Indian Power Sector, in which Tool to demonstrate step wise approach for
Namely, the total capacity of off- grid power plants (in MW) should be at least 10 per cent of the total capacity of grid power plants in the electricity system; or the total electricity generation	calculation of OM and BM. The database considered only grid- connected power stations for OM & BM calculations and it	the calculation of OM and BM is followed. VVB has cross checked the same by checking the Central
by off-grid power plants (in MWh) should be at least 10 per cent of the total electricity generation by grid power plants in the electricity system; and that factors which negatively	has been specifically mentioned that Small decentralised generation sets; Stations or units installed in Andaman	Electricity Authority of India published a database named "CO2 Baseline database for the Indian Power Sector provided by the
affect the reliability and stability of the grid are primarily due to constraints in generation and not to other aspects such as transmission capacity.	and Nicobar Islands and Lakshadweep; Captive power stations and Non- conventional renewable energy	PP and by checking online. Theus the condition is met.
	stations are currently not accounted for in the database.	This samelities is not
(c) In case of CDM projects the tool is not applicable if the project electricity system is located partially or totally in an Annex I country.	This condition of tool is not applicable as GCC accepts project from worldwide whereas under CDM only non-Annex-1 country can submit projects and hence tool is referring to Annex-1	This condition is not applicable in GCC projects as GCC accepts project from worldwide.
(d) Under this tool, the value applied to the CO2 emission factor of biofuels is zero.	The project is a wind project and does not involve any biofuels.	The condition is not applicable for the bundled project.
Applicability conditions of "Tool 2 project activities version 13.1"	21: Demonstration of ac	ditionality of small scale
Applicability criteria of the tool 21, Version 13.1	Justification in the PSF	DOE assessment
The use of the methodological tool "Demonstration of additionality of small-scale	The project owners do not propose any new methodology	The project owner do not propose any new methodology and has

project activities" is not mandatory for project participants when proposing new methodologies. Project participants and coordinating/managing entities may propose alternative methods to demonstrate additionality for consideration by	and applied the existing small-scale methodology, AMS ID, version 18. Therefore, this tool has been appropriately applied.	applied the existing small-scale methodology, AMS ID, version 18. Thus the condition has met.
the Executive Board. Project participants and coordinating/managing entities may also apply "TOOL19: Demonstration of additionality of microscale project activities" as applicable.	The Bundled project is not a microscale project activity. With a cumulative capacity of 10 MW, it falls under the category of a small-scale project. The additionality of the project has been demonstrated through the use of Tool 27: Investment analysis. Hence, the application of this tool is deemed appropriate.	This condition is not applicable for this bundle project.
Applicability conditions of "TOOL 2 Applicability criteria of the tool TOOL 27: Investment Analysis version 11.		
This methodological tool is applicable to project activities that apply the methodological tool "Tool for the demonstration and assessment of additionality", the methodological tool "Combined tool to identify the baseline scenario and demonstrate additionality", the guidelines "Non-binding best practice examples to demonstrate additionality for SSC project activities", or baseline and monitoring methodologies that use the investment analysis for the demonstration of additionality and/or the identification of the baseline scenario.	The project owners have identified "investment barrier" as one of the barriers faced by the Bundled project, as per Tool 21. Consequently, the applicability of this methodological tool is justified for the Bundled project.	barrier" as one of the barriers faced by the bundled project activit and the same has been explained in the PSF .
In case the applied approved baseline and monitoring methodology contains requirements for the investment analysis that are different from	AMS I.D. Ver 18 does not contain requirements for the investment analysis that are different from	This condition is met as the applied methodology does not contain any requirements for the

those described in this methodological tool, the requirements contained in the methodology shall prevail.	investment analysis.

D.3.2 Clarification on applicability of methodology, tool and/or standardized baseline

Means of Project Verification	Not applicable
Findings	No findings
Conclusion	Not applicable

D.3.3 Project boundary, sources and GHGs

Means of Project Verification	Desk Review and on-site inspection			
Findings	No findings			
Conclusion	According to the approved baseline and monitoring methodology "AMS-I.D" of "Grid connected renewable electricity generation", version 18 /B02/, the project boundary is "the spatial extent of the project boundary includes the project power plant and all power plants connected physically to the electricity system that the CDM project power plant is connected to". The physical boundary of the project activity identified by the project owner has been cross-verified by site visit observation /17/, commissioning report for the power plant /5/ and power purchase agreement /4/. In section B.3 of the PSF /01/, project boundary has been adequately stated in figure 4 and table. Hence, the project boundary covers the wind power plant and the other power plants which connected to the related electricity system and the Indian National Grid.			

D.3.4 Baseline scenario

Means of Project Verification	Desk Review and on-site inspection			
Findings	CAR03 and CAR04 has been raised			
Conclusion	According to the approved baseline methodology AMS-I.D version 18 /B02/, "The baseline scenario is that the electricity delivered to the grid by the project activity would have otherwise been generated by the operation of grid-connected power plants and by the addition of new generation sources into the grid." Project activity involves generation of electricity using wind power plant and selling it to Indian National grid as confirmed through the power purchase agreement /4/ and commissioning report /5/. In the absence of this project activity, same amount of electricity would have been generated by the operation of existing/proposed grid connected fossil fuel-based power plants. The same was cross checked and confirmed by the grid emission factor data published in the CEA database version 17.0 /18/.			

to produce electricity and supply to the grid. In the absence of the project activity, the equivalent amount of power would have been generated by the operation of grid-connected power plants and by the installation of additional generation sources. Hence, the baseline for the project activity is the equivalent amount of power displaced from the Indian grid as a result of the project activity."
The following ex ante parameters and assumptions were used to estimate baseline emissions of the project activity. Combined margin CO2 emission factor for the project electricity system in year y $(EF_{grid,CM,y})$ – The value has been calculated and published in the CEA database version 17.0. The value is calculated as per the TOOL 07: "Tool to calculate the emission factor for an electricity system" (Version 07.0). This was found in accordance with the methodology.
 CCPIL project verification team was able to verify all the documented evidence listed above during the GCC Project verification process and can confirm that: All the assumptions and data used by the project participants are listed in the PSF, including their references and sources; All documentation used /4/ /5/ /18/ are relevant for establishing the baseline scenario and correctly quoted and interpreted in the PSF; Relevant national and/or sectoral policies and circumstances are considered and listed in the PSF /1/;
The approved baseline methodology AMS-I.D, version 18, has been correctly applied to identify the most reasonable baseline scenario and the identified baseline scenario reasonably represents what would occur in the absence of the proposed GCC project activity.

D.3.5 Demonstration of additionality

Means of Project	Desk Review and on-site inspection			
Verification				
Findings	CL05, CL06, CL09, CL16, CAR05, CAR06, and CAR07 has been raised			
Conclusion	Project Participant has described the Demonstration of additionality according to the GCC Project Standard Version 03.1. In section B.5 of the PSF, two components are applied for the demonstration of additionality.			
	 (i) Legal Requirement Test: The project activity is a Type A project and requires undergoing a Legal Requirement Test. However, the projects as in the project activity are not mandated by law or regulations and are entirely a voluntary action. The project is additional as per paragraph 46 of GCC Project Standard V3.1. 			
	(ii) Additionality Test: To cover this requirement from the GCC Project Standard 3.1, section 6.4.8, paragraph 45 and as per the applied methodology AMS-1.D version 18.0, additionality of the following project activity is demonstrated and assessed by the latest version of Tool 21: Demonstration of additionality of small-scale project activities version 13.1 /B05/.			
	As per the para 10 of tool 21, project owner shall provide an explanation to show that the project activity would not have occurred anyway due to at least one of the following barriers: a) Investment barrier b) Technological barrier			

c) Barrier due to prevailing practiced) Other barrier
The project owner has identified "investment barrier" as the most relevant barriers faced by the project activity. This is in compliance with the para 10 of Tool 21.
The investment analysis has been used to determine whether the project bundled project is economically or financially less attractive than other alternatives without additional funding that may be derived from the sale of carbon credits. The investment barrier faced by the project consists of barrier due to high capital cost and consequent impact on return. The investment analysis is conducted in accordance with Tool 27: investment analysis, version 12.
The purpose of investment analysis is to determine whether the project activity is economically or financially less attractive than other alternatives without additional funding that may be derived from the sale of carbon credits. The investment barrier faced by the project activity consists of barrier due to high capital cost and consequent impact on return. The investment analysis is conducted in accordance with Tool 27: investment analysis, version 11.
Considering the fact that the alternative to the project is the supply of electricity from the grid & the choice of the developers is to invest or not to invest, benchmark analysis has been considered appropriate for demonstration of additionality, which is in conformity with Investment Analysis. Project owners have considered Equity IRR as the suitable financial indicator for investment analysis
Para 15 of investment analysis states that Required/expected returns on equity are appropriate benchmarks for an equity IRR. Therefore, the Expected return on equity is considered appropriate benchmark.
As per the para 15 of Tool 27: Investment analysis, version 12.0, 'Required/expected returns on equity are appropriate benchmarks for an equity IRR' /B06/. Project owner has used the default benchmark value mentioned it the Appendix of Tool 27: Investment analysis. Project owner has Version 12.0, the default value was revised to a more conservative 9.77% for group 1 projects in India. Recognizing the more conservative nature of Version 12.0's values, the project owners appropriately chose to use this version for benchmark calculations. Consequently, they also considered the same tool to determine the default value of return on equity for their respective projects. Further para 16 of the tool 27 states that "In situations where an investment analysis is carried out in nominal terms and the available IRR benchmarks are in real terms, project participants shall convert the real term values of benchmarks to nominal values by adding the inflation rate. The inflation rate shall be obtained from the inflation forecast of the central bank of the host country for the duration of the central bank shall be used. If this information is also not available, then the average forecasted inflation rate for the host country published by the IMF (International Monetary Fund World Economic Outlook) or the World Bank for the next five years after the start of the project activity shall be used". The equity IRR calculated is nominal equity IRR. Accordingly, project owner converted the default benchmark which is in real terms by using the following equation;
Nominal Benchmark = {(1+Real Benchmark) x (1+Inflation rate)}-1
The GCC Project verification team referred the book 'Corporate Finance: Theory and Practice', 2nd edition, by 'Aswath Damodaran'/19/. In page 320 of the book, the same equation is mentioned for converting real into nominal values. Hence the GCC Project verification team considers the above equation as appropriate for converting

	real benchmark into nominal benchmark. Project owner has sourced from Inflation forecast for India as per IMF which was available at the time of investment decision.					
a se Dye This com " A r activ envi 1. S	The investment analysis has been done based on the project ownership. Therefore a separate benchmark calculation and sensitivity analysis has been done for Roha Dyechem Pvt. Ltd and Arkas Energy LLP. This has been carried out to maintain the homogeneity of the bundle and is in compliance with the para 11 of GCC clarification no.1, which states that "A homogeneous bundle shall be formed based on the analysis of multiple activities to find out similarity in technological, economic and environmental/methodological considerations. These are explained as follows. 1. Similarity in Technological Consideration 2. Similarity in Economic and Policy Consideration.					
				vestors profile are different the investment bundles as follows.		
The The	chmark Calcula investment decisi inflation forecas age from 2016 to	sion date t as per IN	was 19/05/			
Norr	inal Benchmark	estimated	d = {(1+9.7	7) x (1 + 5.30%)}-1 = 15.59%		
the t	CCIPL team verified all the above said details and documents; and confirmed that the benchmark identified to compare the financial attractiveness of the project activity is appropriate.					
	The key Parameters available at the time of investment decision (19/05/2016) considered by Roha for computing post tax Equity IRR are tabulated below:					
	Parameter Unit Value Source/ remark					
	Capacity of the project	6	MW	As per purchase order (PO) which was available around the time of investment decision.		
	Plant Load Factor	18.30	%	As per energy yield estimate report		
	Annual Net generation	9.62	GWh	Calculated		
	Project cost 337.50 INR As per PO Million					
	Debt	70	%	As per MPERC tariff order- March 2016		
	Equity	30	%	As per MPERC tariff order- March 2016		
	Interest rate	12	%	As per MPERC tariff order- March 2016		
	Debt Repayment tenure	10.5	Years			
	Moratorium	0.5	Years			
	Operation and	5.4	INR Million	As per INOX offer		

Maintenance (3rd year)			
Escalation in O & M	5	%	As per INOX offer
Service tax	15.00	%	As per prevailing tax rates
Tariff	4.78	INR/KW h	As per MPERC tariff order- March 2016
IT Depreciation Rate	80.00	%	Indian Tax laws
Income tax rate	34.61	%	Indian Tax laws
MAT rate	21.34	%	Indian Tax laws

The equity IRR calculations were provided in a spreadsheet /03/. The calculation was verified and found to be correct by CCIPL project verification team; as well as the assumptions used in the calculation were deemed to be correct. The post-tax equity IRR without GCC carbon credit revenues is 4.98% which confirms that the proposed project activity in absence of the GCC carbon credit benefits and compared to the benchmark return on equity 15.59% (post tax) is not financially attractive.

A sensitivity analysis has been carried out for parameters contributing more than 20% revenues and costs, to demonstrate the robustness of the financial analysis. The parameters for which sensitivity analysis done are annual power generation (PLF), change in tariff, project costs and operational and maintenance cost. Sensitivity analysis was conducted for $\pm 10\%$ variation. Reasonable variations for these parameters were checked by calculating the variation necessary to reach the benchmark and then discussing the likelihood for that to happen.

Sensitivity analysis for Roha Dyechem Pvt. Ltd.

Parameter	-10%	Normal	10%	Breaching Value
Tariff	2.84%	4.98%	7.32%	45.00%
PLF	2.84%	4.98%	7.32%	45.03%
Project Cost	7.08%	4.98%	3.46%	-34.98%
O&M Cost	5.35%	4.98%	4.61%	-340.06%

Tariff:

The Power Purchase Agreement (PPA) between Roha and the state DISCOM was signed at the same tariff rate of Rs. 4.78 per unit, which Roha had considered during its investment decision-making process.

It was verified that with a significant 10% increase in tariff, the Equity Internal Rate of Return (IRR) remains below the Cost of Equity.

PLF:

It was verified that the highest achieved PLF has only reached 12.55%. Actual

-	generation data for this bundled project has been checked. Hence increase in PLF upto 45% to breach the benchmark is not possible.						
Th	Project Cost: Though the actual cost was less than the initial assumption, but further reductions in project costs are unlikely, given that the project has already been implemented. Moever further reduction of 34.98% to breach the benchmark is not possible.						
Ho O& ag are Ta	O&M Cost: However, during the sensitivity analysis, it has become evident that reducing the O&M cost would result in breaching the benchmark at negative values. O&M agreements signed between Roha and Inox Wind, clearly indicate that O&M costs are subject to escalation. Taking these agreements into consideration, any significant reduction in O&M costs is hypothetical and not practical.						
	nchmark Calcula e investment deci						
	e inflatation forec ar average from 2			e time of investment decision is 5.53% (5			
No	Nominal Benchmark estimated = {(1+9.77) x (1 + 5.53%)}-1 = 15.85%						
the	CCIPL team verified all the above said details and documents; and confirmed that the benchmark identified to compare the financial attractiveness of the project activity is appropriate.						
	The key Parameters available at the time of investment decision (25/05/2015) considered by Arkas for computing post tax-Equity IRR are tabulated below:						
	Parameter	Unit	Value	Source/ remark			
	Capacity of the project	4	MW	As per purchase order			
	Plant Load Factor	18.30	%	As per INOX energy yield estimate report			
	AnnualNet generation6.41GWhCalculatedProject cost234.00INR MillionAs per PODebt70%As per MPERC tariff order-control period FY 2013- 2016						
	Equity	30	%	As per MPERC tariff order-control period FY 2013- 2016			
	Interest rate	14.41	%	Average BPLR of the five public sector banks applicable to project at the time of			
				investment decision			

Debt Repayment tenure	10	Years	As per MPERC tariff order-control period FY 2013- 2016
Moratorium	1	Years	As per MPERC tariff order-control period FY 2013- 2016
Operation and	2.3	INR Million	As per MPERC tariff order-control period FY 2013- 2016
Maintenance (3rd year)			
Escalation in O & M	5.72	%	As per MPERC tariff order-control period FY 2013- 2016
Service tax	15.00	%	As per prevailing tax rates
Tariff	5.92	INR/KW h	As per MPERC tariff order-control period FY 2013- 2016
IT Depreciation Rate	80.00	%	Indian Tax laws
Income tax rate	34.61	%	Indian Tax laws
MAT rate	21.34	%	Indian Tax laws

The equity IRR calculations were provided in a spreadsheet /03/. The calculation was verified and found to be correct by CCIPL project verification team; as well as the assumptions used in the calculation were deemed to be correct. The post tax equity IRR without GCC carbon credit revenues is 8.41% which confirms that the proposed project activity in absence of the GCC carbon credit benefits and compared to the benchmark return on equity 15.85% (post -tax) is not financially attractive.

A sensitivity analysis has been carried out for parameters contributing more than 20% revenues and costs, to demonstrate the robustness of the financial analysis. The parameters for which sensitivity analysis done are annual power generation (PLF), change in tariff, project costs and operational and maintenance cost. Sensitivity analysis was conducted for $\pm 10\%$ variation. Reasonable variations for these parameters were checked by calculating the variation necessary to reach the benchmark and then discussing the likelihood for that to happen.

The results of the sensitivity analysis for Arkas are summarized below:

Parameter	-10%	Normal	10%	Breaching Value
Tariff	5.75%	8.41%	11.01%	26.67%
PLF	5.75%	8.41%	11.00%	26.70%
Project Cost	11.17%	8.41%	6.22%	-21.70%
O&M Cost	8.68%	8.41%	8.14%	-263.15%

Tariff:

The Power Purchase Agreement (PPA) was signed at a reduced tariff of Rs. 4.78

per unit, reflecting the updated regulatory framework when compared to the rate Rs. 5.92 per unit considered at the time of investment decision. To offset the impact of the reduced tariff, Arkas took advantage of the Generation-Based Incentive (GBI) benefits available to wind electricity producers. This agreement ensures that power will be sold at a pre-fixed price, making any upward adjustments beyond this predetermined rate unlikely. It was verified that with a significant 10% increase in tariff, the Equity Internal Rate of Return (IRR) remains below the Cost of Equity.
PLF: It was verified that the highest achieved PLF has only reached 12.55%. Actual generation data for this bundled project has been checked. Hence increase in PLF upto 26.70% to breach the benchmark is not possible.
Project Cost: Though the actual cost was less than the initial assumption, but further reductions in project costs are unlikely, given that the project has already been implemented. Moever urther reduction of 21.70% to breach the benchmark is not possible.
O&M Cost:
However, during the sensitivity analysis, it has become evident that reducing the O&M cost would result in breaching the benchmark at negative values. O&M agreements signed between Arkas and Inox Wind, clearly indicate that O&M costs are subject to escalation. Taking these agreements into consideration, any significant reduction in O&M costs
is hypothetical and not practical.
It is evident from the results given above; the bundled project remains additional even under the most favorable conditions.

D.3.6 Estimation of emission reductions or net anthropogenic removal

Means of Project Verification	Desk Review and on-site inspection					
Findings	No findings					
Conclusion	Baseline Emission According to AMS I.D methodology, emission reductions related to project activities is estimated as follows:					
	$BE_y = EG_{PJ,y} \times EF_{grid,CM,y}$ Where: $BE_y = Baseline emissions in year y (t CO2/yr)$					
	$EG_{PJ,Y}$ = Quantity of net electricity generation that is produced and fed into the grid as a result of the implementation of the project activity in year y (MWh/yr)					
	$EF_{grid,CM,y}$ = Combined margin CO ₂ emission factor for grid connected power generation in year y calculated using the latest version of the "Tool to calculate the emission factor for an electricity system Version 7.0" (t CO2/MWh)					
	The annual average electricity generation over the crediting period has been calculated and given in ER Sheet /02/. According to ER Sheet, EG _{PJ,Y} is 16,031 MWh/yr. Also, According to CEA database, the emission factor (<i>EFgrid</i> , <i>CM</i> , <i>y</i>) could be used as 0.9310 tCO2/MWh.					

Therefore, BE _y = 16,031 MWh/year x 0.9310 BE _y = 14,925 tCO2e
Project Emissions (PEy) As the project activity is a WTG based power generation, the project emissions are not applicable to the project activity as per the methodology AMS I.D. /B02/.
Hence, PEy = 0
Leakage (LEy) As per AMS I.D. /B02/, no leakage emissions are considered.
Therefore, $LEy = 0$.
Emission Reductions Based on the data above, the emission reduction value for the project activity is:
$ER_y = BE_y - PE_y - LE_y$
$ER_y = BE_y = 14,925 \text{ tCO2e}$

D.3.7 Monitoring plan

Means of Project	Desk Review and on-site inspection				
Verification					
Findings	CL02, CL04, CL10, CAR08, and CAR09 has been raised				
Conclusion	The approved baseline and monitoring methodology "AMS-I" version 18 /B02/ has been applied. The monitoring plan is in accordance with the monitoring methodology; the monitoring plan will give opportunity for real measurement of achieved emission reductions. CCIPL project verification team has checked all the parameters presented in the monitoring plan against the requirements of the methodology; no deviations relevant to the project activity have been found in the plan. CCIPL confirms that the monitoring arrangements described in the monitoring plan are feasible within the project design, and the means of implementation of the monitoring plan are sufficient to ensure the emission reductions achieved by/resulting from the proposed GCC project activity can be reported ex post and verified. Parameters available at the time of project verification (ex-ante) (Mention under section B.6.2 of the PSF) are:				
	Parameter Value Unit Assessment				

Operating Margin CO ₂ emission factor in year y of Vietnam national Grid. (EF _{grid} ,om,y)	0.9518	tCO2e/MWh	Generation weighted average, sourced from Baseline CO2 Emission Database, Version 18.0, september 2022 published by Central Electricity Authority (CEA), Government of India /18/. The ex-ante vintage data has been used for the OM calculation of the project. The value has been ccalculated as the last 3-year (2019- 20, 2020-21 and 2021-22) generation-weighted average, sourced from Baseline CO2 Emission Database, Version 18.0, September 2022 published by Central Electricity Authority (CEA), Government of. India .The simple OM is fixed ex-ante in line with the 'tool to calculate the emission factor for an electricity system" Version 07.0.0 /B04/. Hence, accepted by the project verification team.
Build Margin CO ₂ emission factor in year y of Vietnam national Grid (EF _{grid,ВМ,у})	0.8687	tCO2e/MWh	Calculated as per the latest datageneration weighted average, sourced from Baseline CO2 Emission Database, Version 18.0 september 2022 published by Central Electricity Authority (CEA), Government of India. As per the "tool to calculate the emission factor for an electricity system" Version 07.0.0 /B04/, the build margin emissions factor is the generation-weighted average emission factor (tCO ₂ /MWh) of all power units <i>m</i> during the most recent year <i>y</i> for which electricity generation data is available. Hence, the value has sourced from CEA database version 18 /38/. The calculation procedures are outlined in the PSF /1/. Hence, accepted by the project verification team.
Combined Margin CO ₂ emission factor in year y of Vietnam National Grid (EF _{grid,СМ,у})	0.9310	tCO2e/MWh	Calculated CO2 Emission Database, Version 18.0,September 2022 published by Central Electricity Authority (CEA), Government of India. Government of India. The value is calculated considering 75% operating margin and 25% build margin as per the "tool to calculate the emission factor for an electricity system" Version 07.0.0 /B04/.
Parameters that wi are:	II be monito	bred (ex-post) (Mention under section B.7.1 of the PSF

The approved baseline and monitoring methodology "AMS-ID" version 18 /B02/ has been applied. The monitoring plan is in accordance with the monitoring methodology; the monitoring plan will give opportunity for real measurement of achieved emission reductions. CCIPL project verification team has checked all the parameters presented in the monitoring plan against the requirements of the methodology; no	
presented in the monitoring plan against the requirements of the methodology; no deviations relevant to the project activity have been found in the plan.	

CCIPL confirms that the monitoring arrangements described in the monitoring plan are feasible within the project design, and the means of implementation of the monitoring plan are sufficient to ensure the emission reductions achieved by/resulting from the proposed GCC project activity can be reported ex post and verified.

Parameters that will be monitored (ex-post) (Mention under section B.7.1 of the PSF are:

Parameter	Value	Unit	Assessment
EG _{PJ,Y} (SDG-7) (Quantity of Net Electricity supplied by the project plant/unit to the grid in year y)	16,031	MWh	The estimated net electricity generated is given, however, the value for the parameter will be verified through review of on-site meter reading records. <i>The meter details and the calibration</i> <i>frequency have been cross verified</i>
	Pa	arameters relat	ed to SDGs
SDG 3: The number of health camps held and the number of people who have received health care service	To be determi ned at the time of verificati on/issua nce.	Numbers	Project owner will conduct health camps. The number of people received health care services will be verified during emission reduction verification.
GSDG 4- Ensure inclusive and equitable quality education and promote lifelong learning opportunities for all:	To be determi ned at the time of verificati on/issua nce.	Amount spend in INR	The total expenses incurred towards facilitating education/ infrastructure support will be verified during emission reduction verification and the steps that will be followed by the project owner is mentioned in the table under section B.7.1. The same will be verified during emission reduction verification.
SDG 6- Ensure availability and sustainable management of water and sanitation for all	To be determi ned at the time of verificati on/issua nce.	Amount spent in INR	Expenses incurred towards sanitation and safe drinking water facilities will be verified during emission reduction verification. To monitor progress toward SDG 6 (Clean Water and Sanitation), PO will follow this plan: - Monitor infrastructure quality and budget allocation. PO will

			 monitor the construction and maintenance of water and sanitation facilities and will keep records of the allocated budget for water and sanitation projects. Ensure water quality through regular testing. PO will conduct regular water quality tests to ensure that water sources meet safe drinking water standards and are free from contaminants Feedback: PO will collect feedback and assess community satisfaction with the provided services.
			The same is mentioned under table of section B.7.1 in the PSF and deemed acceptable and will be verified during emission reduction verification.
SDG8: Number	To be	Number	The bundled Project will generate
of people employed	determi ned at		local employment. This will be an indicator against sustainable
during project	the time		development goal SDG 8. The
construction	of		parameter will be verified through
and project	verificati		employee records/contracts.
operation.	on/issua		
	nce.		
SDG 13- SDG 13-	Cumulat ive emissio n reductio n for 10- year crediting period – 149160 tCO2e	tCO2e/Year	The project activity will result in emission reduction. The same will be contributing toward the sustainable development goal SDG 13. The parameter will be verified through emission reduction calculation sheet.
SDG 15- To	To be	Amount	The number of trees planted and the
counteract desertification, the company will arrange plantation drives	determi ned at the time of verificati on/issua	spent in INR	number of trees that survived will be used to assess the impact of the planting drives, which will be verified during emission reduction verification
at schools and other community locations in the	nce.		
area.			
	Parameters	related to Envi	ronmental safeguards
CO2 Emission:	Cumulat	tCO2/Year	The project activity will result in
Reduction of CO2 emissions due to	ive emissio n	1002/1001	emission reduction. The same will be contributing toward the environmental safeguards parameter
		1	en en en eguardo paramotor

of the project activity not 10- year crediting period - 149180 verified through emission reduction calculation sheet Replacing fossil fuels 16031 to 22e MWh/Year to 22e The estimated net electricity generated is given, however, the sources of energy: Quantity of net electricity supplied by the project plant/unit to the grid in year y MWh/Year to 10 to 10 years) The estimated net electricity generated is given, however, the value for the parameter will be verified through review of on-site meter reading records. Vear y Parameters related to sources of plant/unit to the grid in year y Not provided Number The number of long term employees employeed from the salary slips , employeed for more than one year Sources of income generated due to the project activity Not provided Number The number of employees activity will be verified drom the salary slips , employeed from the salary slips , employeed for more than one year Reducing accidents: Number of Employment generated due to the project activity Not provided Number Total number of persons trained on operational and safety protocols will be verified drom training records on personel trained during emission reduction verification Specialized training (SE01) Not provided Amount spent in INR Training records on personel trained during emission reduction verified during emission reducti		n	r	1
fuels with renewable sources MWh (Averag generation energy: Quantity of net electricity supplied by the project generation on for 10 electricity plant/unit to the grid in years) generated is given, however, the value for the parameter will be verified through review of on-site meter reading records. Verary Parameters related to Social safeguard Long-term jobs (> 1 year) Not provided Number The number of long term employees will be verified from the salary slips , employment records/contracts during emission reduction verification Womber verary Not provided Number The number of employment generated due to project activity will be verified during emission reduction verification Number of employeed for more than one year Not provided Number The number of employment generated due to project activity will be verified during emission reduction verification Number of Employment generated due to the project activity Not provided Number Total number of persons trained on operational and safety protocols will be verified during emission reduction verification Specialized on operational and safety Not provided Amount spent in INR Training records on personnel trained on plan operation and maintenance will be verified during emission reduction verification Bird hits/ bird mortality may NA NA The records of bird mortality and actors taken will be verified during emission reduction	activity	year crediting period – 149160 tCO2e		calculation sheet
Long-term jobs (> 1 year) created: Number of Person employed for more than one yearNot providedNumberThe number of long term employees will be verified from the salary slips , employment records/contracts during emission reduction verificationSources yearof providedNot providedNumberThe number of employment generated due to project activity will be verified during emission reduction verificationNumber generated to the project activityNot providedNumberTotal number of persons trained on operational and safety protocols will be calculated from training record and/or confirmation from contractual service agency which will be verified during emission reduction verificationReducing accidents: providedNot providedNumber providedTotal number of persons trained on operational and safety protocols will be calculated from training record and/or confirmation from contractual service agency which will be verified during emission reduction verificationSpecialized toical personnel (SEO1)Not Monitoring-program of risk management actionsTraining records on personnel trained on plant operation and maintenance will be verified during emission reduction verificationBird hits/ bird mortalityNANAThe records of bird mortality and actions taken will be verified during emission reduction verification	fuels with renewable sources of energy: Quantity of net electricity supplied by the project plant/unit to the grid in	MWh (Averag e annual generati on for 10 years)		generated is given, however, the value for the parameter will be verified through review of on-site meter reading records.
(> 1 year) created: Number of Person employed for more than one year number of Person will be verified from the salary slips , employment records/contracts during emission reduction verification Sources of income generation increased: Number of Employment generated due to the project activity Not provided Number provided The number of employment generated due to project activity will be verified during emission reduction verification Reducing accidents: Number of Persons trained on operational and safety Not provided Number Total number of persons trained on operational and safety protocols will be calculated from training record and/or confirmation from contractual service agency which will be verified during emission reduction verification Specialized training / education to local personnel (SEO1) Not provided Amount spent in INR Training records on personnel trained on plant operation and maintenance will be verified during emission reduction verification Bird hits/ bird mortality: Bird mortality may NA The records of bird mortality and actions taken will be verified during emission reduction verification		Parame	eters related to	Social safeguard
Sources income generation increased: Number of Employment generated due to the project activityNot providedNumber providedThe number of employment generated due to project activity will be verified during emission reduction verificationReducing accidents: Number of Persons trained on operational and safety protocolsNot providedNumber providedTotal number of persons trained on operational and safety protocols will be calculated from training record and/or confirmation from contractual service agency which will be verified during emission reduction verificationSpecialized training / education to local personnel (SE01)Not providedAmount spent in INRTraining records on personnel trained on plant operation and maintenance will be verified during emission reduction verificationBird hits/ bird mortality: Bird mortality: mortalityNANAThe records of bird mortality and actions taken will be verified during emission reduction verification	(> 1 year) created: Number of Person employed for more than one		Number	will be verified from the salary slips , employment records/contracts during
accidents: Number of Persons trained on operational and safety protocolsprovidedoperational and safety protocols will be calculated from training record and/or confirmation from contractual service agency which will be verified during emission reduction verificationSpecialized training (seo1)Not providedAmount spent in INRTraining records on personnel trained on plant operation and maintenance will be verified during emission reduction verificationMonitoring-program of risk management actionsMonitoring-program of risk management actionsBird mortality: mayNANAThe records of bird mortality and actions taken will be verified during emission reduction verification	Sources of income generation increased: Number of Employment generated due to the project		Number	generated due to project activity will be verified during emission reduction
Specialized training education local personnel (SE01)Not providedAmount spent in INRTraining records on personnel trained on plant operation and maintenance will be verified during emission reduction verificationMonitoring-program of risk mortality: mortality mayNANAThe records of bird mortality and actions taken will be verified during emission reduction verification	accidents: Number of Persons trained on operational and safety		Number	operational and safety protocols will be calculated from training record and/or confirmation from contractual service agency which will be verified during emission reduction verification
Bird hits/ bird mortality:NANAThe records of bird mortality and actions taken will be verified during emission reduction verification	Specialized training / education to local personnel (SE01)	provided	spent in INR	on plant operation and maintenance will be verified during emission reduction verification
mortality: Bird mortality may actions taken will be verified during emission reduction verification	I	wormoning-p		
	mortality: Bird	NA	NA	actions taken will be verified during

collision with the rotating blades of the WTGs. If there is any bird mortality, the PO will keep track of it			
Noise Pollution	NA	NA	Noise level in surrounding community would be checked by communicating with residents of neighboring villages to ensure there is no noise pollution
Hazardous Waste, E- Waste, End-of- Life Equipment	NA	NA	The documents showing following information will be verified during emission reduction verification from O& M contractor : The Quantity of hazardous waste handled safely; Equipment safely disposed away once its useful life is over; Quantity of e- waste handled safely
against the require	ments of the erification to	e monitoring meam that the m	ted in the project activity and compared nethodology /B02/. It has been nonitoring plan, procedures, roles and ed to be feasible.

D.4. Start date, crediting period and duration

Means of Project Verification	Desk Review and on-site inspection
Findings	No findings
Conclusion	The start date of the project is 10/06/2016, which is the start date of commercial operation of the project /5/. Crediting period has been chosen as fixed 10 years from 01/08/2016 to 31/07/2016. A fixed crediting period of length of 10 years has been selected by project proponent. Therefore, the duration of the crediting period is from 01/08/2016 to 31/07/2016 Technical lifetime for the project activity is 25 years /4/. The project verification team concludes that the duration of the proposed project activity is in conformance with the requirements of §39 and §40 of GCC Project Standard, version 03.01 /B01-A/.

D.5. Environmental impacts

Means of P	Project	Desk Review and on-site inspection
Verification		
Findings		No findings
Conclusion		As per the guidelines on Environmental Impact Assessment have been published by Ministry of Environment, Forests and Climate Change (MoEF&CC), Government of India (GOI) under Environmental Impact Assessment notification 14/09/2006 and further amendments to the notification have been done on 14/07/2018 /38/. As per the notification wind generation projects are not listed in any of the categories of the schedule, So, the project is considered environmentally safe and as per Host party- India no Environmental Impact Assessment is required to be carried out.

The project will benefit the local people by engaging them in construction, operation
and maintenance activities during the project. The verification team also confirm
that the project owner has taken all the necessary legal approvals from the
government and other parties to implement the project activity.

D.6. Local stakeholder consultation

Means of Project Verification	Desk Review and on-site inspection
Findings	No findings
Conclusion	It has been indicated in the PSF /1/ that the local stakeholder consultation has been done for the project activity on 28/05/2022 at the project site. That is before the commissioning of the project activity. The meeting announcement was done by putting public notice at project site/nearby village. The same covers meeting location, date, time, and contact information/15/. A summary of comments has been provided by project owner in the PSF/1/ and it is found that no adverse comment was received for the project activity. This has also been verified by CCIPL project verification team during site visit /17/. Further, the interviews confirmed that there was no adverse comment about the project and this project will lead to employment generation and better environmental conditions. CCIPL considers the local stakeholder consultation carried out adequately and can confirm that the process is in line with the requirements of GCC.
	Moreover, it was also confirmed that a grievance register is available at the sarpanch's (Village Head) office as part of an ongoing mechanism for the local stakeholders to express their grievances and ask questions about the project. The company representatives examine the register's contents at least once a month and are in charge of resolving any questions or concerns that local stakeholders may have about the project.

D.7. Approval and Authorization- Host Country Clearance

Means of Project Verification	Desk Review and on-site inspection
Findings	No findings
Conclusion	The verification team confirms that no HC approval is required by the CORSIA labelled project activity till 31/12/2020, and the HCA will be required during the first or subsequent verification

D.8. Project Owner- Identification and communication

Means of Project Verification	Desk Review and on-site inspection	
Findings	CL11 has been raised	
Conclusion	Organization name	Roha Dyechem Private Limited
	Country	India
	Address	A 44/45, Road No. 2, M.I. D.C., Andheri E, Mumbai,
		Maharashtra
		400093 IN
	Telephone	+91-9823240000, +91-9413203573
	Fax	-
	E-mail	rohagccprojects@rohagroup.com
	Website	https://www.rohagroup.com

Contact norsen (primar	Chrikipan Phytoda, Maanakahi Jain	
Contact person (primary	/ Shrikisan Bhutada, Meenakshi Jain	
contact)		
Organization name		
Organization name	Arkas Energy LLP	
Country	India	
Address	14, Link Road, Jangpura Extension, New Delhi – 110014	
Telephone	+91-9413203573	
Fax		
E-mail	meenakshi@positiveclimatecare.com	
Website		
Contact person	Ashish Jain, Meenakshi Jain	
project owners themselves the PSF which was checked letter signed by the project documents. The project ver certificate/19/ of Roha Dye Dyechem private limited an project. The project verifica MP Pashimk shetravitaran letter and the company inc team thus confirmed the le verification team has check that Positive Climate Care	information and contact details of the representation of the project owner and project owners themselves has been appropriately incorporated in Appendix 1 of the PSF which was checked and verified by the verification team from Authorization letter signed by the project owners. All information was consistent between these documents. The project verification team has reviewed the company registration certificate/19/ of Roha Dyechem private limited and Arkas Energy LLP and Roha Dyechem private limited and Arkas Energy LLP has the legal ownership of the project. The project verification team has reviewed Commissioning certificate from MP Pashimk shetravitaran Co. Ltd/5/. The registration number mentioned in the letter and the company incorporation certificate is same. The project verification team thus confirmed the legal ownership of the wind project activity. The project verification team has checked the LOA /16/ submitted by the client and confirms that Positive Climate Care Private Limited is the authorized external representative of proposed project activity developed Roha Dyechem private limited and Arkas Energy LLP	

D.9. Global stakeholder consultation

Means of Project	Desk Review and on-site inspection
Verification	
Findings	No findings
Conclusion	The process for global stakeholder consultation was conducted in accordance with the requirements of section 3.2.4 of the Verification Standard (version 03.1) /B01-B/. The PSF was published for global stakeholder consultation from 08/09/2022 to 22/09/2022.During the above period no Global stakeholders' comments were received.

D.10. Environmental Safeguards (E+)

Means of Project Verification	Desk Review and on-site inspection
Findings	CL12, an CL13 has been raised
Conclusion	The Project owner has chosen to apply for the Environmental No-net-harm Label (E+). The assessment of the impact of the project activity on the environmental safeguards has been carried out in section E.1 of the PSF. Out of all the safeguards no risks to the environment due to the project implementation were identified and the following environmental impacts were considered for the project activity. (a) Environment – Air; CO2 emissions

The project is expected to reduce the CO2 emission throughout the crediting period. Therefore, DO NO Harm Risk assessment is evaluated as harmless. However, based on the monitoring approach adopted by the project owner, the scoring is +1. This is accepted by the project verification team.

(b) Environment – Natural Resources; Protecting/enhancing species diversity The chances of Bird hit will be recorded and action will be taken if the bird hit is found to occur during the implementation of the project activity. PO has provided the monitoring procedure for this parameter as they will maintain a register to track the birds mortality that will be tracked by a regular visit on site by the assigned persion for the same. The parameter is on a least risk as project area does not come under any ecological sensitive zone therefore this scenario is less likely to occur and the same has been explored by the VVB to confirm the sensitivity of bird harm in thr location.The scoring is provided as +1. This is accepted by the project verification team.

(c) Environment – ; Replacing fossil fuels with renewable source of energy In absence of the project activity, the equivalent amount of electricity would be generated from the operation of grid-connected power plants, which is GHG intensive. The project activity generates and supplies renewable Wind sourced based electricity to the grid, where it replaces fossil fuel source-based electricity, thus the project activity is unlikely to cause any harm and is assessed as harmless. However, based on the monitoring approach adopted by the project owner, the scoring is +1. This is accepted by the project verification team.

(d) Environment _ Noise pollution

Bundled project may generate sound (noise) pollution due to operation of wind turbines disturbing the habitat around the project area. For this project owner is using upgraded, Blade design and controlled rotation in high wind conditions reduce aerodynamic noise emanating from the movement of air around the turbine blades and tower. Further, the Double-Fed Induction Generator Technology used in Inox wind turbine is such that generation of the noise from the nacelle is minimal, therefore this scenario is less likely to occur.

For this project owner will track the parameter "Noise level in surrounding community". Every year they will track the noise level in the surrounding area. Despite the fact that there are currently no surrounding communities within hearing distance of the project, noise pollution is not a problem. A logbook will be kept in the surrounding community to track complaints about noise levels in the event that new residential areas are built during the crediting period. , the scoring is +1. This is accepted by the project verification team.

(e) Environment - Hazardous Waste, E-Waste, End-of-Life Equipment

Foll all types of waste generated project owner will contract with a third party O &M contactor to dispose the wastes. The quantity of waste wastes generated and the waste disposed will be recorded during the monitoring period by the project owner. the scoring is +3. This is accepted by the project verification team.

The verification team confirm that the project activity will not cause any net harm to the environment and net score for project activity comes out to be +7

D.11. Social Safeguards (S+)

Means of Project	Desk Review and on-site inspection
Verification	
Findings Conclusion	CL14, and CL15 has been raised The Project owner has chosen to apply for the Social No-net-harm Label (S+). The assessment of the impact of the project activity on the social safeguards has been carried out in section E.2 of the PSF. Out of all the safeguards no risks to the Society due to the project implementation were identified and the following have been indicated as positive impacts. The verification team based on the review of the PSF and the supporting document/15/ confirms that the social impacts mentioned in the section E.2 of the PSF is applicable to the Project activity and the monitoring procedures of the parameters are provided.
	(a) Social -Jobs; Long term jobs (> 1 year) created/lost The project activity leads to employment generation in long term during the construction period. Employment records can be verified during the emission reduction verification. The numbers of job provided will be tracked by the project owner by checking the employment records and by tracking the same with the O& M contractor from their employment record. The number of jobs generated will be defined during verification. The same could be verified with the human resource records of the project owner during emission reduction verification.
	(b) Social -Jobs; Sources of income generation increased / reduced The project activity leads to creating local employment generation in the project region. It creates the additional sources of income for the people employed for the project activity. Employment records, services contacts/job contracts can be verified during the emission reduction verification. The same could be verified with the human resource records, purchase department records of the project owner during emission reduction verification.
	(c) Social-Health and Safety: Reducing/Increasing incidents During construction and operational phase, the training on health and safety requirements including the trainings related to working at heights will be imparted. Other precautionary measures such as allowing only certified workers to install, maintain or repair electrical equipment and providing personal protective equipment will be carried out during the operational phase. The safety and accident prevention training records can be verified during emission reduction verification.
	(d) Social – Education; Educational services improved or not The project owners will work to improve education services in the surrounding area by choosing from a variety of initiatives based on the recognised needs of the project area. Providing Financial support for female child education, as well as using donations to purchase school materials for impoverished students are two such examples. The funds set aside for such initiatives will be recorded and can be verified during emission reduction verification.
	Verification team will be able to confirms that Project activity will not cause any net harm to the society and net score for project activity comes out to be +4. Refer CL 18

D.12. Sustainable development Goals (SDG+)

Means of Project Verification	Desk Review and on-site inspection
Findings	No findings
Conclusion	The Project owner has chosen to apply for the United Nations Sustainable Development Goals (S+). The assessment of the impact of the project activity on the SDG's has been carried out in section F of the PSF. The project is expected to contribute 8 SDGs which are SDG 3, 4, 6, 7, 8, 13, and 15 The verification team confirms that the SDG chose by the project owner is in compliance with the GCC Project sustainability standard V.3.1 and is applicable to the Project activity and the monitoring procedure of each SDG is given in section F and B.7.1 of the PSF.
	UN- level SDGs (a) Goal 3. Ensure healthy lives and promote well-being for all at all ages. The project owner has voluntarily opted to implement SDG goal 03 by organizing health camps in rural areas where access to health care facilities remains an issue. At least one health camps per year will be organized to provide free health checks and educate locals about health and hygiene issues thereby complying with SDG target 3.8.
	(b) Goal 4. Ensure inclusive and equitable quality education and promote lifelong learning opportunities for all. The project owner has voluntarily opted to implement SDG goal 04 by implementing initiatives in the project area such as providing financial support for girl child education, book distribution in government schools, infrastructure support for government schools, organizing vocational training and skill development programs to boost self-employment. The initiatives meets the SDG target 4.3 and 4.4.
	(d) Goal 6. Ensure availability and sustainable management of water and sanitation for all. The project owner has voluntarily opted to implement SDG goal 06 by implementing initiatives such as construction of handwashing facilities, installation of RO systems, installation of feminine hygiene facilities at the project location. Thes initiatives meets the SGD target 6.1 and 6.2
	(e) Goal 7. Ensure access to affordable, reliable, sustainable and modern energy for all The project activity that commissioned on 10/06/2016 continues to provide clean energy to the global energy mix, annually generating around 16,031 MWh of renewable energy using Wind energy thereby complying with the SDG target 7.2.
	(f) Goal 8. Promote sustained, inclusive and sustainable economic growth, full and productive employment and decent work for all The project activity is found to be generating employment during construction and operational phase, thereby complying to the SDG target 8.6 and 8.8.
	(g) Goal 13. Take urgent action to combat climate change and its impacts. The project activity reduces greenhouse gas annually by 14,925 tCO ₂ meeting the SDG target 13.2 and 13.3.
	(h) Goal 15. Protect, restore and promote sustainable use of terrestrial ecosystems, sustainably manage forests, combat desertification, and halt and reverse land degradation and halt biodiversity loss.

The project owner has voluntarily opted to implement SDG goal 15 by implementing vegetation plantation drives at schools and other communities in the project location to fight against soil and land degradation and to counteract desertification. These initiatives meets the SDG target 15.3
During interview with the project owner VVB confirms that no SDG under the bundle project comes under the CSR of the project activity and the declaration by the project owner for the same has been provided to the VVB. Refer CL 17 and CCL 19.

D.13. Authorization on Double Counting from Host Country (for CORSIA)

Means of Project Verification	Desk Review and on-site inspection				
Findings	No findings				
Conclusion	A declaration under section A.5 of the PSF has been included for offsetting the approved carbon credits (ACCs) for the entire crediting period from 01/08/2016 to 31/07/2026 The host country attestation is yet to be obtained for authorization on double counting. The project activity is neither registered nor seeking registration in any carbon offsetting program; hence the approved carbon credits (ACCs) from this project activity shall not be double counted.				

D.14. CORSIA Eligibility (C+)

Means of Project Verification	Desk Review and on-site inspection
Findings	FAR 1 has been raised
Conclusion	The project activity meets the CORSIA Eligibility since the crediting period is after 01/01/2016 and the project is applying for registration under GCC which is one of the approved programmes for eligibility. It was also confirmed that the project activity does not fall under the excluded unit types, methodologies, programme elements, and/or procedural classes.

Section E. Internal quality control

The Final Verification report has undergone a technical review and quality review before being submitted to the project owner. A technical reviewer is qualified in accordance with CCIPL's qualification scheme for GCC verification performed the technical review.

Section F. Project Verification opinion

CCIPL was contracted by Roha Dyechem Private Limited for project verification of the project activity "Wind Power Project Activity in MP, India". The project verification was performed based on rules and requirements defined by GCC for the project activity.

The project activity is a grouped Wind power project, which results in reductions of CO_2e emissions that are real, measurable and give long-term benefits to the mitigation of climate

change. It is demonstrated that the project is not a likely baseline scenario and the emission reductions attributable to the project are, hence, additional to any that would occur in the absence of the project activity. The project correctly applies the approved baseline and monitoring AMS-1.D, Version 18.0 and is assessed against latest valid PS, VS and Environment and Social Safeguards Standard, Project-Sustainability-Standard and/or other applicable GCC/CDM Decisions/Tools/Guidance/Forms.

The project activity is likely to achieve the anticipated emission reductions stated in the PSF provided the underlying assumptions do not change. The expected emission reductions (annual average) from the project activity are estimated to be 14,925 tCO₂e/year over the 10 years crediting period starting from 01/08/2016.

CCIPL has informed the project owners of the project verification outcome through the draft project verification report and final project verification report. The final project verification report contains the information with regard to fulfilment of the requirements for project verification, as appropriate.

CCIPL applied the following verification process and methodology using a competent verification team;

• the desk review of documents and evidence submitted by the project owner in context of the reference GCC rules and guidelines issued,

• undertaking/conducting site visit, interview, or interactions with the representative of the project owner reporting audit findings with respect to clarifications and non-conformities and the closure of the findings, as appropriate.

- preparing a draft verification opinion based on the auditing findings and conclusions
- technical review of the draft project verification opinion along with other documents as appropriate by an independent competent technical review team
- finalization of the project verification opinion (this report)

Carbon Check (India) Private Limited (CCIPL) has verified and hereby certifies that the GCC project activity "Wind Power Project Activity in MP, India"

(a). has correctly described the Project Activity in the Project Submission Form (version 3.0, dated 04/09/2023) including the applicability of the approved methodology AMS-1.D, version 18.0 and meets the methodology applicability conditions, is additional and is expected to achieve the forecasted real and additional GHG emission reductions, complies with the monitoring methodology, has appropriately conducted local and global stakeholder consultation processes and has calculated emission reduction estimates correctly and conservatively.

(b). is likely to generate GHG emission reductions amounting to the estimated 149,250 tCO₂e as indicated in the PSF, which are additional to the reductions that are likely to occur in absence of the Project Activity and complies with all applicable GCC rules, including ISO 14064-2 and ISO 14064-3, and therefore requests the GCC Program to register the Project Activity;

(c.) is not likely to cause any net-harm to the environment and/or society and complies with the Environmental and Social Safeguards Standard, and therefore requests the GCC Program to register the Project Activity, which is likely to achieve the requirements of the Environmental No-net-harm Label (E+) and the Social No-net-harm Label (S+); and

(d). is likely to contribute to the achievement of United Nations Sustainability Development Goals (SDGs), comply with the Project Sustainability Standard, and contribute to achieving a total of 8 SDGs, which is likely to achieve the Diamond SDG certification label (SDG+)

e. is likely to contribute to CORSIA Eligible Emission Units and has CORSIA Label (C+) certification valid till 31 December 2020. A written attestation from the Host country on double counting is not required until 31 December 2020 and the project was found meeting the applicable requirements prescribed by ICAO.

Abbreviations	Full texts			
ACC	Approved Carbon Credits			
ACM	Approved Consolidated Methodology			
AM	Approved Methodology			
AMS	Approved Methodology for SSC Projects			
BE	Baseline Emission			
BM	Build Margin			
CAR	Corrective Action Request			
CCIPL	Carbon Check (India) Private Limited			
CDM	Clean Development Mechanism			
CH ₄	Methane			
CL	Clarification Request			
СМ	Combined Margin			
CO ₂	Carbon dioxide			
СР	Crediting Period			
DR	Desk Review			
EIA	Environmental Impact Assessment			
ERVR	Emission Reduction Verification Report			
ERVT	Emission Reduction Verification Team			
FAR	Forward Action Request			
GCC	Global Carbon Council			
GHG	Green House Gas			
GW	Giga Watt			
GWh	Giga Watt hour			
IPCC	Intergovernmental Panel on Climate Change			
kW	Kilo Watt			
KWh	Kilo Watt hour			
LSC	Local Stakeholder Consultation Process			
MoV	Means of Verification			
MP	Monitoring Plan			
MW	Mega Watt			
MWh	Mega Watt hour			
ОМ	Operating Margin			
PSF	Project Submission Form			
PE	Project Emission			
PLF	Plant Load Factor			


Appendix 1. Abbreviations


Project Verification Report

PMR	Project Monitoring Report
PO	Project Owner
PSF	Project Submission Form
RFR	Request for Registration
SDG	Sustainable Development Goal
tCO ₂ e	Tonnes of Carbon dioxide equivalent
TPH	Tonnes Per Hour
UNFCCC	United Nations Framework Convention on Climate Change
V	Version
VS	Verification Standard

Appendix 2. Competence of team members and technical reviewers

		Carb — CHEC	on «——	
Carbo	on Check	(India)	Private	Limited
	Certificat	e of Con	npetenc	y
	Ms. Apc	arna Cho	udhary	
-				ance with the requirement pplicable GHG programs:
	for the follow	ing functions and re	equirements:	
🛛 Validator	🛛 Verifier	🛛 Team Lea	der	🛛 Technical Expert
Technical Reviewer	🗆 Health Expert	🗆 Gender E	xpert	🗆 Plastic Waste Expert
⊠ SDG+	🛛 Social no-harm(S+) 🛛 Environm	nent no-harm(E+)	CCB Expert
🗆 Financial Expert	🛛 Local Expert for	India		
	in the f	ollowing Technical .	Areas:	
🖂 TA 1.1	🖾 TA 1.2	🗆 TA 2.1	🖾 TA 3.1	🗆 TA 4.1
🗆 TA 4. n	🗆 ТА 5.1	🗆 TA 5.2	🗆 TA 7.1	🗆 TA 8.1
🗆 ТА 9.1	🗆 ТА 9.2	🗆 TA 10.1	🖾 TA 13.1	🖾 TA 13.2
🗆 TA 14.1	🗆 TA 15.1			
Issue	Date		Expi	ry Date
03 rd Ma	ay 2023		04 th N	lay 2024
Virash &	Sil		Λ	مرکلس
Mr. Vikash Kumar Singh Mr. Amit Anand Compliance Officer CEO				





No.	Author	Title	References to the document	Provider
/1/	PO	PSF Version 01 dated 16/06/2022 Version 03 dated 04/09/2023		PO
/2/	PO	Emission reduction spreadsheet Version 03 dated 04/09/2023		PO
/3/	PO	Investment analysis sheet		PO
/4/	PO	Power purchase agreement	28/09/2016	MP power managem ent company limited
/5/	PO	Commissioning certificate	15/06/2016	MP PaschimK shetraVita ran Co Ltd
/6/	PO	Calibration certificates		M.P.P.K. V.V CO. LTD
/7/	PO	Purchase Order evidences	25/06/2015 and 30/09/2016	
/8/	PO	Operations and maintenance 12/12/2017 contracts		
/9/	PO	Land ownership documents	16/12/2015	
/10/	PO	Inox records		
/11/	PO	Plant load factor evidence		
/12/	PO	El approval		
/13/	PO	Hazardous waste management evidences		
/14/	PO	Project layout and location		
/15/	PO	Local stakeholder consultation evidences	21/05/2022	
/16/	PO	Letter of Authorization		
/17/	VVB	On site visit document		
/18/	CEA	CEA CO2 baseline emission database version 18.0		
/B01/	GCC	A. GCC Project Standard, version 3.1 B. GCC Verification Standard, version 3.1 C. GCC Program Manual, version 3.1 D. Environment-and-Social- Safeguards-Standard, version 3.0 E. Project-Sustainability-Standard, version 3.1		
/B02/	UNFCCC	AMS-I.D.: Grid connected Version 18.0 C renewable electricity generation		Others
/B03/	GCC	PSF template	Version 4.0	Others

Appendix 3. Document reviewed or referenced

/B04/	UNFCCC	Tool 07: Tool to calculate the emission factor for an electricity system	Version 07	Others
/B05/	UNFCCC	Tool 21: Demonstration of additionality of small-scale project activities	Version 13.1	Others
/B06/	UNFCCC	Tool 27: Investment analysis	Version 11.	Others

Appendix 4. Clarification request, corrective action request and forward action request

Table 1. CLs from this Project Verification

CL ID	01	Section no.	B.2	Date: 03/06/2023		
Description of CL						
Referring methodolo in the stat PO has m as it is a renewable As it has relevance Project O	to the applic ogy and its justi tement provided nentioned in sec new grid con e energy genera been observe of above ment Wner's respor	fication provided in the d and actual implement ction B.2 of PSF that " nected renewable win ation units at an existin d that the project act ioned statement in PS	e section B.2 of PSF, VVE tation of the project activi This condition is not appl ad project activity and do ng renewable power gene tivity is a greenfield pow SF.	Cable to the project activity bes involve the addition of pration". The plant, PO is clarify the Date: 07/07/2023		
of renewa	able energy ge has been mad	eneration units to an e in the revised PSF.		oes not involve the addition er generation facility. This		
Documer	ntation provide	ed by Project Owner				
GCC Pro	ject Verifier as	sassmant		Date: 24/08/2023		
			which clarifies that the pr	oject is a green field activity		
			ty thus the finding has be	, , ,		
			•			
		Continue		D -to- 02/00/2000		
CL ID	02	Section no.	B.7.2	Date: 03/06/2023		
Descripti	on of CL					
Descripti As per th	on of CL e article 6, para	6.1.3 of PPA, "Meters	s and metering equipment	procured by seller shall be		
Descripti As per the tested as	on of CL e article 6, para per provisions	6.1.3 of PPA, "Meters of MPERC and as pe	s and metering equipment			
Descripti As per the tested as before ins	on of CL e article 6, para per provisions stallation at site	of 6.1.3 of PPA, "Meters of MPERC and as pe on the cost of seller".	s and metering equipment er IS 14697 at CPRI or a	procured by seller shall be		
Descripti As per the tested as before ins PO is requ	on of CL e article 6, para per provisions stallation at site uested to clarify	6.1.3 of PPA, "Meters of MPERC and as pe on the cost of seller". / how this condition ha	s and metering equipment er IS 14697 at CPRI or a	procured by seller shall be t any NABL accredited lab		
Descripti As per th tested as before ins PO is req Project O	on of CL e article 6, para per provisions stallation at site uested to clarify wner's respon	6.1.3 of PPA, "Meters of MPERC and as pe on the cost of seller". how this condition ha	s and metering equipment er IS 14697 at CPRI or a as been met.	procured by seller shall be		

All five wind turbines were commissioned on June 10th, 2016. The meters and metering equipment underwent testing in 2015, conducted by the meter testing division of Madhya Pradesh Paschim Kshetra Vidyut Vitran Company Limited (MPPKVV Co. Ltd.). The test reports have been submitted to the Verifier.

Documentation provided by Project Owner *Meter Test Reports*

GCC Project Verifier assessment

Date: 24/08/2023

PO has submitted the meter test reports conducted by the meter testing division of Madhya Pradesh Paschim Kshetra Vidyut Vitran Company Limited (MPPKVV Co. Ltd.). that clarifies that the condition is met as stated in article 6, para 6.1.3 of PPA.

CL ID	03	Section no.	NA	Date: 03/06/2023		
Description of CL						
				oject Owners shall ensure that the		
				ent GCC rules and requirements		
				including Project Activity design,		
				urther, as per paragraph 65 of the		
				ct Owners shall make available to		
				description, evidence of their right		
				or implementation of measures".		
		e the following docun	nentary evidence to	VVB		
	Authorization	and the second		1-		
		ata from commissioni	ng upto present dat	te.		
3. Installat		ocupting				
	tion on double	-	dooumont			
	· · · ·	Investment decision ing the input values for the input value values for the input value value value values for the input value				
	vner's respon			Date: 07/07/2023		
		cuments have been p	provided to the verif			
		d by Project Owner				
	Authorization					
		ata from commissioni	na up to June 2022			
3. Installat			5 /			
	ion on double	counting.				
5. Investment decision document						
6. All the documents relating the input values for the calculation of IRR						
GCC Project Verifier assessment Date: 24/08/2023						
Project owner has provided all the required supporting documents that has been checked by the						
verifier and thus the finding has been closed.						

CL ID	04	Section no.	B.7.4	Date: 03/06/2023			
Descriptio	Description of CL						
Referring to	o the article 6, para 6	3.3, of PPA, "In	case there are different sel	lers owning the WEGs at			
			n these WEGs is fed into the				
			by a common billing meter				
			required to be done at the co				
		or crediting of t	he generated units and sha	aring of Reactive Energy			
changes ac							
	PO is requested to clarify if there are any other projects whose power is fed in to the same delivery						
point as that of the proposed project activity. If so, PO is requested to clarify how the compliance as							
	per the above paragraphs has been met.						
Project Ow	/ner's response			Date: 07/07/2023			

At the Chandwasa site, there are three project wind turbines (WTGs) named P-42, P3-87, and P3-88. In addition to these, two more WTGs named P-48 and P-63 are connected to a common metering point. The main meter installed at this common metering point measures the electricity generated and consumed by all five wind turbines collectively. Marut Shakti Energy India Ltd., the developer, apportions the export and import meter readings based on the individual wind turbine's controller generation. The developer generates a monthly generation and consumption report which includes the export and import data of each individual wind investor. This report is then signed by the officials from the electricity distribution company (DISCOM) of the Madhya Pradesh (MP) state. Based on this monthly generation report, each investor raises an invoice to the MP State DISCOM for the units exported to the grid.

Similarly, at the Dalmu site, there are three wind turbines named P72, P-73 (project WTGs) and P-74 (other investor) connected to the Dalmu common metering point. The cumulative power generated by all three wind turbines is measured at the common metering point, and the monthly generation and consumption are apportioned based on the individual wind turbine's controller data. This process is carried out in a similar fashion as described for the Chandwasa site.

Documentation provided by Project Owner

GCC Project Verifier assessment

Date: 24/08/2023

Based on the explanation provided by the project owner above it is clear to the verifier that 5 WGTs are connected to the common metering point, However, the Marut Shakti Energy India Ltd., the developer, apportions the export and import meter readings based on the individual wind turbine's controller generation. The developer generates a monthly generation and consumption report which includes the export and import data of each individual wind investor. This report is then signed by the officials from the electricity distribution company (DISCOM) of the Madhya Pradesh (MP) state. Based on this monthly generation report, each investor raises an invoice to the MP State DISCOM for the units exported to the grid and the same procedure to detect the monthly generation for each individual WGT has been followed in the Dalmu site as well.

VVB has also cross verify the supporting documents provided by the project owner and interviewed the plant managers physically to confirm the same. This the finding has been closed.

CL ID	05	Section no.	B.5	Date: 03/06/2023		
Description	of CL					
Background	d: requirements of p	aragraph 38 ai	nd 40 (b) of the GCC projec	t standard, version 3.1.		
AS per the	para 7.1.1, Article 7	of PPA, the i	tariff provided is 4.78INR/K	Wh, which is as per the		
MPERC tar	iff order dated 17/0	03/2016 applic	able for wind energy proje	ects commissioned from		
01/04/2016	to 31/03/2019. Also	, 7.1.3 of Artic	le 6 states that, "The tariff i	rates shall be firm for the		
			exchange rate or on accour			
any other re	any other reason whatsoever". But, the tariff mentioned in the section B.5 of PSF is 5.92 INR/KWh					
for the calculation of Equity IRR for Arkas.						
PO is requested to clarify the discrepancy between the value provided in PSF and PPA.						
Project Ow	ner's response			Date: 07/07/2023		

Arkas took the decision to invest in the project activity on May 25, 2015, while the prevailing MPERC tariff order dated March 2013 was applicable for the control period from April 1, 2013, to March 31, 2016. According to this tariff order, the Commission set the tariff at Rs. 5.92 per unit for generation from new wind energy projects commissioned during the above control period. Arkas considered this tariff while making their investment decision.

On the other hand, Roha made the decision for the project activity on May 19, 2016, when the MPERC tariff order dated March 2016 was prevailing. Roha considered a tariff of Rs. 4.78 per unit while deciding on their investment.

It's worth noting that both the companies made their investment decisions based on different tariff orders that were applicable during the respective timeframes. Arkas considered the tariff order from 2013, while Roha considered the tariff order from 2016.

Documentation provided by Project Owner

GCC Project Verifier assessment

Based on the explanation provided by the project owner it is clear to the verifier that project owner has applied the tariff based on the prevailing conditions applicable during the investment decision dated of the respective sites.

CL ID	06	Section no.	B.5	Date: 03/06/2023
Description	of CL			

PO is requested to clarify how the project activity complies with article 7.4 of the PPA (Sharing CDM benefits). PO is also requested to clarify how the same has been considered in the investment analysis, as per paragraph 27 under Section B.4 of the GCC PSF Filling guidelines. Date: 07/07/2023

Project Owner's response

According to Article 7.4 of the Power Purchase Agreement (PPA), there is a provision for sharing CDM (Clean Development Mechanism) benefits with the electricity procurer, which in this case is MP Power Management Co. Ltd. However, as mentioned in Section A.5 of the PSF, the project activity is not registered nor seeking registration under CDM. Therefore, the clause regarding sharing of CDM benefits with the electricity procurer is not applicable to the project owners.

However, in the future, if the MP government demands sharing of revenue received from the sale of Approved Carbon Credits (ACCs), the project owners will comply with the government's requirements.

Documentation provided by Project Owner

GCC Project Verifier assessment

Based on the explanation provided by the project owner and after checking the CDM website it is confirmed that the project is not seeking to register under the CDM and thus the clause of sharing the CDM benefits to electricity procurer is overcome. However in the future, if the MP government demands sharing of revenue received from the sale of Approved Carbon Credits (ACCs), the project owners will comply with the government's requirements that shall be checked by the VVB during monitoring verification.

CL ID	07	Section no.	A.1/A.2	Date: 03/06/2023
Description	Description of CL			

Date: 24/08/2023

Date: 24/08/2023

Based on the review of the PSF, Power purchase agreement, commissioning certificate, the location of the WTGs mentioned in these documents are found to be inconsistent between each other. Refer to the table below for details.

1. WTGs	2. Location		
	3. PSF	4. PPA	5. Commissioning certificate
6. NPY P-42 7. NPY P3- 87	 Village-Bhaguniya & others, Tehsil - Garoth/Shamgarh, District Mandsaur 	 12. Village Chandwasa and Bhatuni, Tehsil- Sharmgarh, District 13. Mandsaur 	 14. Village-Bhaguniya & 15. others, Tehsil - 16. Garoth/Shamgarh, District 17. Mandsaur
18. NPY P3- 88	 19. Village - Bhaguniya & 20. others, Nipaniya Tehsil - 21. Garoth/Shamgarh, District 22. Mandsaur 	23. Village Garada, Tehsil Shamgarh, District 24. Mandsaur	 25. Village - Bhaguniya & 26. others, Nipaniya Tehsil - 27. Garoth/Shamgarh, District 28. Mandsaur
29. NPY P-72 30. NPY P-73	31. Village - Detli Bujurg, 32. Tehsil- Garoth, District 33. Mandsaur	34. Village Dethali Bujurg, Tehsil- Garoth, District- Mandsaur	

PO is requested to clarify the discrepancy in the location of WTGs NPY P-42, NPY P3-87, NPY P3-88 between PSF and PPA.

Moreover, in the section A.2 of PSF, PO has mentioned the name of only one village as project location (Village Bhaguniya), while the project is located in villages Bhaguniya and Detli Bujurg, as per section A.1 of PSF. PO is requested to provide consistent data representation throughout PSF.

Also, in section A.2 of PSF, PO is requested to provide the geo coordinates of the Substations.

Project Owner's response

Date: 07/07/2023

In the case of WTG location numbers NPY P-42, NPY P3-87, and NPY P3-88, the commissioning certificate mentions the village name as Bhaguniya & others, which is adjacent to Chandwasa Substation. However, the Power Purchase Agreement (PPA) specifies the exact village names for the respective machines. Initially, the Project Owner (PO) cited the locations in PSF based on the commissioning certificates. However, in the revised PSF, the village names have been corrected according to the PPA.

Regarding WTG location numbers NPY P-72 and NPY P-73, a discrepancy exists due to a difference in the spelling of the village name. The commissioning certificate states the village as 'Detli,' while the PPA mentions it as 'Dethli.' The village name has been corrected in the revised PSF according to the PPA.

Documentation provided by Project Owner

GCC Project Verifier assessment

Date: 24/08/2023

Based on the explanation provided by the PP and crosschecking the same with the geocoordinates provided by the project owners for each WGT the reason for the discrepancies is now clear to VVB and the same has been revised by the project owner in the PSF.

CL ID	08	Section no.	A.3	Date: 03/06/2023
Description	n of CL			
Project Owr	ner is requested to c	omply with the	requirements of all the para	agraphs of the section A3
of the GCC	PSF Filling instruction	ons.		
The followin	ng technical specifica	ations are found	d to be missing in the table	provided in section A.3 of
PSF,				
1. Rated wil	nd speed			
2. Number of	of blades			
3. Rotor spe	eed, max			
4. Rotor ma	terial			
5. Generato	or details.			
PO is reque	ested to add the sam	e in the specifie	ed section	
Project Ow	ner's response			Date: 07/07/2023
The technic	al specifications mer	ntioned above h	ave been included in Table	in section A.3 of the PSF.
Documenta	ation provided by P	roject Owner		
GCC Projec	ct Verifier assessm	ent		Date: 24/08/2023
Project own	er has now added a	all the parameter	ers with their specifications	in the section A.3 of the
PSF, thus th	ne finding has been o	closed.	-	

CL ID	09	Section no.	B.5	Date: 03/06/2023
Description	of CL			
			TOOLOT I I I I	

As per paragraph 10 of CDM Methodological tool: TOOL27: Investment analysis.

"Input values used in all investment analysis shall be valid and applicable at the time of the investment decision taken by the project participant. The DOE is therefore expected to validate the timing of the investment decision and the consistency and appropriateness of the input values with this timing. The DOE should also validate that the listed input values have been consistently applied in all calculations." This approach raises concern on the overall investment analysis and input parameters in particular. PP is

requested to clarify this, while doing so, please provide evidence for.

- 1. input value used for the investment analysis.
- 2. all documents as stated in annexure 1 of VVB plan.

3. third party energy yield assessment report for PLF considered for ER estimation and for Investment analysis.

4. The sources/link of the IMF inflation forecast, which is not provided in the PSF.

Project owner is requested to comply to the requirements of paragraph 49 and 50 of the GCC project standard Version 3.1 and paragraph 10 & 16 of CDM Methodological tool: TOOL27: Investment analysis In the section B.5 of PSF, PO has provided the annual net generation value as 9.62 GWh and PLF as 18.30%. PO is requested to provide the source to VVB as it has been observed that the source has not been provided. Also, the source is requested to be mentioned in the PSF.

Project Owner's response

Date: 07/07/2023

All the supporting documents for input values used for the investment analysis, including the INOX's energy yield estimate report report for Plant Load Factor (PLF) considered in the analysis, have been provided to the Verifier. The source or link of the IMF forecast and the PLF value considered is already included in the PSF. This ensures transparency and supports the credibility of the investment analysis.

Documentation provided by Project Owner

Copies of all the following documents have been provided for your reference:

1. Purchase Orders

2. Inox Wind Energy Yield Estimation Report

3. MPERC Tariff Order for the Control Periods of 2013-2016 and 2016-2019, which were applicable at the time of investment decision.

4. For Arkas, the Average Benchmark Prime Lending Rate (BPLR) of the five public sector banks, applicable at the time of their investment decision

5. Tax Rates prevailing at the Time of Investment Decision

6. A copy of the offer provided by Inox to Roha

GCC Project Verifier assessment

Date: 24/08/2023

VVB has crosschecked all the supporting documents provided by the project owner to verify the input values considered for the calculation of the IRR and to check on the investment decision date as pet the requirements of tool 27, the documents provided by the owner is sufficient to check the same. Thus the finding has been closed.

CL ID 10 Section no. B.7.4

Date: 03/06/2023

Description of CL

It has been observed that PO has provided single line diagram of the the project activity with its metering location in the section B.7.4 of PSF. However, based on the review of the commissioning certificate, it has been observed that the WTGS NPY P- 42, NPY P3-87, NPY P3-88 are connected to the step up transformer at Chandwasa grid system and WTGs NPY P-72, NPY P-73, are connected to the step up transformer at Dhalma Grid System. PO is request to represent this in the provided line diagram.

Project Owner's response

In section B.7.4 of the PSF, a line diagram depicting both the common metering points at the Chandwasa and Dalmu sites has been provided.

Documentation provided by Project Owner

GCC Project Verifier assessment

Date: 24/08/2023

Date: 07/07/2023

Project owner has provided a line diagram In section B.7.4 of the PSF, depicting both the common metering points at the Chandwasa and Dalmu sites.

CL ID	11	Section no.	NA	Date: 03/06/2023		
Description	of CL					
Background	I: requirements of pa	aragraph 38 an	d 40 (b) of the GCC project	t standard, version 3.1.		
It has been	observed that the p	ower purchase	agreement has been sign	ed by the project owners		
(Arkas Enel	rgy LLP/ Roha Dye	echem Pvt Ltd	as seller), Madhya Prade	esh Power Management		
Company L	Company Limited (as procurer) and Marut Sakthi Energy India Limited (as developer). PO is					
requested to clarify the involvement of Marut Sakthi Energy India Limited in the project activity.						
Project Ow	ner's response			Date: 07/07/2023		

Global Carbon Council

Marut-Shakti Energy India Limited is one of the six subsidiaries of Inox Wind Infrastructure Services Limited (IWISL). The project owners have entrusted Marut-Shakti with the important tasks of facilitating the purchase of land and providing power evaluation services at windmill sites. Additionally, Marut-Shakti is responsible for apportioning the energy generated at the common metering point and supplying the project owners with monthly energy generation and consumption data.

Documentation provided by Project Owner

GCC Project Verifier assessment

Project owner has explained the role of the Marut-Shakti Energy India Limited as one of the six subsidiaries of Inox Wind Infrastructure Services Limited (IWISL). The project owners have entrusted Marut-Shakti with the important tasks of facilitating the purchase of land and providing power evaluation services at windmill sites. Additionally, Marut-Shakti is responsible for apportioning the energy generated at the common metering point and supplying the project owners with monthly energy generation and consumption data. Thus the finding is closed.

CL ID	12	Section no.	E.1	Date: 03/06/2023	
Description	of CL				
Background	I: Project owner is re	equested to co	mply to the requirements o	f paragraph 21 and 22 of	
the GCC Pr	oject Sustainability S	Standard versic	n 3.		
			ental safeguard "Environr		
			as mentioned that the Bird r		
however it is	s not clear that which	n procedure/me	ethod will be used to monito	r the parameter.	
Project Ow	ner's response			Date: 07/07/2023	
			an employee of the Project		
	visits at predetermined intervals. During these visits, he meticulously documents his findings in a				
dedicated re	dedicated register. This practice is explicitly mentioned in both Section B.7.4 and Section E.1 of the				
PSF					
Documenta	Documentation provided by Project Owner				

GCC Project Verifier assessment Date: 24/08/2023 Project owner has explained the procedure to monitor the bird mortality and the same has been added in the Section B.7.4 and Section E.1 of the PSF. Thus, the finding has been closed.

CL ID	13	Section no.	E.1	Date: 03/06/2023	
Description	of CL				
With reference to the section D and section E.1 (environmental safeguard), PO is requested to briefly explain the measures that has been taken to mitigate the impact on land. This is also with reference to the environmental safeguard "Solid waste pollution from hazardous waste".					
Project Owner's response Date: 07/07/2023					

Date: 24/08/2023

During the handling and disposal of hazardous waste, the Operations and Maintenance (O&M) contractor, appointed by the Project Owners, places a high priority on safety. They take necessary precautions to ensure the safe handling and proper disposal of hazardous waste.

The O&M contractor strictly adheres to the Hazardous and other Wastes (Management & Transboundary Movement) Rules of 2016, ensuring full compliance with the regulations. These rules provide guidelines for the safe management, storage, transportation, and disposal of hazardous waste.

By prioritizing safety and complying with the relevant regulations, the O&M contractor aims to minimize any potential risks associated with the handling and disposal of hazardous waste, protecting both the environment and the well-being of the project's personnel and surrounding communities.

Documentation provided by Project Owner

GCC Project Verifier assessment

Date: 24/08/2023

Project owner has explained explain the measures that has been taken to mitigate the impact on land, reference to the environmental safeguard "Solid waste pollution from hazardous waste" which is deemed acceptable by the VVB thus the finding has been closed.

CL ID	14	Section no.	E.2	Date: 03/06/2023
Description	n of CL			
Background	l: the requiremer	nts of paragraph	12 and 13 of the GC	C Environment and Social
Safeguards	Standard version (03.		
With referen	nce to section E.2, s	social safeguards	s, the PO has provided th	e justification for community
				owner needs to clarify, how
				nile doing so please provide
	dences related to the	he social safegua	ard assessment.	
	ner's response			Date: 07/07/2023
				al community by creating
• •		•••	•	r the residents. Additionally,
				and sanitation in the areas
				onsibility (CSR) activities. It
•		•	•	elopment Goals (SDGs) and
	elfare parameters a			sion of the PSF, community
	ation provided by	<u> </u>	reu separately.	
Documenta				
GCC Proje	ct Verifier assessi	nent		Date: 24/08/2023
As the proj	ect owner is willing	g to provide the	significant contributions	to the local community by
creating en	ployment opportur	nities and suppo	rting skill development i	initiatives for the residents.
Additionally	, the project owner	s have committe	d to investing in education	on, health, and sanitation in
				social responsibility (CSR)
				Boals (SDGs) and contribute
	•			e PSF, community and rural
welfare para	ameters are no long	ger scored separ	ately. Thus the finding ha	as been closed.

CL ID	15	Section no.	E.2	Date: 03/06/2023
Description	of CL			

Backgrou	ind: the requir	rements of paragraph	12 and 13 of t	the GCC Environment and Social
	ds Standard ver			
			parameter Wome	en's empowerment, project owner
				ct to the project activity, while doing
		e evidences related to		
	wner's respon			Date: 07/07/2023
During th	e project's con	struction phase, the	generation of job	bs for women signifies a positive
				d version of the PSF, the specific
		powerment is not score	ed separately.	
Docume	ntation provide	d by Project Owner		
	ject Verifier as			Date: 24/08/2023
The proje	ct owner is now	not scored for the para	meter separately.	. Thus, the finding has been closed.
CL ID	16	Section no.	B 5	Date: 03/06/2023
	ion of CL		<u> </u>	2001 00/00/2020
		ted to comply to the r	equirements of <i>i</i>	paragraph 10 and 28 of the CDM
		DL27: Investment analy		
	-9	,		
PO is red	quested to clari	fy the appropriateness	s of financial ind	licator (Equity IRR for the project)
		project is mainly financ		
Project C	wner's respon	ISE		Date: 07/07/2023
According	to the "Tool for	demonstration and ass	sessment of Addi	tionality", the financial indicator can
				no general preference between the
				IRR over project IRR because It
specifical	ly measures the	e return on the equity	capital invested	in the project. This is crucial for
investors	as they are pr	imarily concerned with	n the return on t	their own investment. Project IRR
				torted results if the capital structure
				ts focus on equity investment and
				rofitability. It also enables them to
				the project's potential to meet their
expectation		sument decisions by di	rectly assessing	the project's potential to meet their
		d by Project Owner		
Documen				
GCC Pro	ject Verifier as	sessment		Date: 08/24/2023
			s deemed accept	table the finding has been closed.
		, , . ,		
				-
				-

CL ID	17	Section no.	B.7.1	Date: 03/06/2023
Description of CL				

Replacing fossil fuel with RE sources shall be mentioned as separate monitoring parameter again under E+/ S+ assessments How the records of expenditures alone would be suitable indicator to monitor the activities under the SDG goals 4. 6 and 15? Justify How salary slips can be used as source to monitor increase in income generation **Project Owner's response** Date: 07/07/2023 To streamline the monitoring process and reduce redundancy, the monitoring of parameters for SDG 7 and the Environmental safeguard parameter "Replacing fossil fuels with renewable sources of energy" have been merged into a single parameter. This consolidation ensures that all references are incorporated into one comprehensive parameter, eliminating the need for separate and continual monitoring of these related aspects. This approach enhances efficiency in monitoring and reporting while still addressing both the SDG and environmental safeguard requirements. PO can verify expenditures related to SDG 4 by providing actual purchase invoices from the school supplies vendor and acknowledgment letters from the local village head (Sarpanch) or school principal confirming the receipt and intended use of educational materials. The expenditures related to SDG 6 can be verified by providing vendor invoices for items such as water tanks, RO water purification units, and wash basins and offering photographs of the installed apparatus or items, including the installation locations' addresses. This evidence confirms the expenses and demonstrates that the purchased items have reached their intended destinations, contributing to clean water and sanitation goals. For SDG 15, the PO will monitor and record the number of trees planted as well as the number of trees that have successfully survived. Salary slips can be used to monitor the increase in income generation resulting from the project activity. They provide quantifiable data, income verification, and documentation of the project's impact on individuals who were previously unemployed, justifying the project's socioeconomic benefits. **Documentation provided by Project Owner** GCC Project Verifier assessment Date: 24/08/2023 Project owner has provided the appropriate explanation for the required clarification and thus the justification is deemed acceptable. Moreover, project owner has also updated the PSF accordingly. Thus the finding has been closed.

CL ID	18	Section no.	E.1	Date: 03/06/2023
Description of CL				

SJ01: need to quantify/ estimate the number of people employed per year

SJ 02: The short term jobs were only during construction (which has been completed), then clarify how it could be monitored during the verification? Clarify?

SJ 03: How it could be quantified and measured that the sources of income has increased? Justify?

SHS03: Need to mention how many trainings would be provided in a year

SH S07, SH S08 are not scored. Then why monitoring details have been provided:

SE01: The parameter is related to training / education to local personnel and not the employees

Project Owner's responseDate: 07/07/2023For this bundled project, a minimum of two personnel has been employed through an O&M
contractor to manage and maintain the project. Additionally, the project owners have hired a
permanent employee at the project site. This permanent employee's role is to oversee and ensure
the effective and efficient execution of all operations and maintenance activities in alignment with
the contractual scope.

The score related to short-term jobs, which were provided only during the construction phase (and have since been completed), has been removed from the revised PSF.

The employment records of the Project Owner (PO) and Operations and Maintenance (O&M) contractor are used to quantify and measure the increase in sources of income. The number of jobs created directly and indirectly through the project activity is closely linked to income generation. When individuals secure jobs through the project, they earn salaries or wages, contributing to their income.

Employees will receive a minimum of one job-specific and one health and safety training session each as part of their training program.

SHS07 activities, which are already covered under SDG 3 monitoring parameters, are not scored separately to avoid double scoring. Similarly, SHS08 activities, which are already addressed under EL02 monitoring parameters, are also not scored separately to prevent double scoring and ensure that the monitoring process remains efficient and accurate.

SE01 acknowledges the provision of specialized training or education to local personnel employed in the bundled project. Given that this specialized training is provided to employees as part of their on-the-job development, it justifies scoring this parameter. This training enhances the skills and capabilities of local personnel, contributing to their professional growth and, in turn, positively impacting the project's overall performance..

Documentation provided by Project Owner

GCC Project Verifier assessment

Date: 24/08/2023

Project owner has justifid the required clarification briefly and thus deemed acceptable by VVB. As the PSF has been updated as per the justification provided, thus the finding has been closed.

CL ID	19	Section no.	F	Date: 03/06/2023
Description	of CL			
whether the	Confirm how SDG related monitoring plan was justified irrespective of the CSR activity? Confirm whether the parameters are described only w.r.t project activity and not as the part of their Company's CSR activity			
SDG 3: mon	itoring plan for achie	eving the health	n coverage.	
	ii) SDG 4: monitoring plan to measure current and future results on improvement of quality of education due to contribution from this project activity			
iii) SDG 6: How money spent for water and sanitation facilities alone can be considered as a monitoring plan?				
iii) SDG 8: Monitoring plan for contribution towards reduction in unemployment due to project activity. Project Owner's response Date: 07/07/2023				
				20101 01/01/2020

The activities listed under section F of the PSF are specified solely in the context of the project activity and are not part of the company's CSR obligations. The PO confirms that these parameters are described exclusively with respect to the project's scope and impact, and they do not constitute or overlap with the company's broader CSR initiatives or responsibilities.

i) In order to monitor progress towards achieving SDG 3, the following monitoring plan will be implemented:

1. Number of Health Camps: PO will keep a record of the total number of health camps organized by the project.

2. People Extended with Healthcare: PO will estimate the number of individuals who have received healthcare services during these health camps. This will be determined from the records maintained for each camp.

By tracking the frequency of health camps and the number of beneficiaries, PO will effectively monitor and assess the project's contribution to improving healthcare access and coverage, aligning with SDG 3 goals.

ii) To monitor the impact of the project on SDG 4 (Quality Education), PO will follow these steps:

- Assess specific educational needs in the project area.

- Select relevant initiatives (e.g., girl child education support, book distribution, infrastructure improvement) based on identified needs.

- Track initiative implementation and ensure alignment with needs. PO will monitor the implementation of selected initiatives, including the allocation of resources, funds, or materials, and ensure that they align with the identified needs.

- Gather feedback from beneficiaries and conduct periodic evaluations. PO will seek feedback from beneficiaries, such as students, teachers, and local communities, to assess the perceived impact of the initiatives on the quality of education.

iii) To monitor progress toward SDG 6 (Clean Water and Sanitation), PO will follow this plan:

- Monitor infrastructure quality and budget allocation. PO will monitor the construction and maintenance of water and sanitation facilities and will keep records of the allocated budget for water and sanitation projects.

- Ensure water quality through regular testing. PO will conduct regular water quality tests to ensure that water sources meet safe drinking water standards and are free from contaminants

- Feedback: PO will collect feedback and assess community satisfaction with the provided services.

iv) To monitor the project's impact on reducing unemployment per SDG 8, PO will follow these steps: Job Creation: PO will track the number of direct and indirect jobs created by the project activity.

Employment Types: PO will categorize the types of jobs created, such as full-time, part-time, temporary, or permanent positions.

Skill Enhancement: PO will monitor any skill development or training programs provided to local community members to enhance their employability.

Employment Duration: PO will track the duration of employment for individuals, emphasizing longerterm employment opportunities.

Documentation provided by Project Owner

GCC Project Verifier assessment

Date: 24/08/2023

As the project owner confirmed that no SDG has come under the CSR responsibility of the bundle project activity and also project owner has appropriately described the monitoring plan for all SDGs and the same has been updated in the PSF. Thus the finding has been closed.

Γ

CL ID	20	Section no.	G.1	Date: 03/06/2023	
Description	n of CL				
Need to me	ntion about the existi	ing stakeholde	r grievance mechanism.		
Project Ow	ner's response			Date: 07/07/2023	
(Village Hea grievances register's co that local sta	During LSC, it was informed to stakeholders that a grievance register is available at the sarpanch's (Village Head) office as part of an ongoing mechanism for the local stakeholders to express their grievances and ask questions about the project. The company representatives examine the register's contents at least once a month and are in charge of resolving any questions or concerns that local stakeholders may have about the project				
Documentation provided by Project Owner					
GCC Project Verifier assessmentDate: 24/08/2023Project owner has updated the PSF with the grievance mechanism followed for the bundle project which is deemed acceptable by the VVB. Thus the finding has been closed.					

CL ID	21	Section no.	C.3.1	Date: 03/06/2023	
Description	of CL				
Clarify why	the crediting period s	start date differ	s from GCC project start da	ite.	
Project Ow	ner's response			Date: 07/07/2023	
			2016 despite the commission of the period beginning in Augu		
			ig penda beginning in Auga	51 2010	
Doodmonte	Documentation provided by Project Owner				
GCC Project Verifier assessment Date: 24/08/2023			Date: 24/08/2023		
The explanation provided by the Project owner is deemed acceptable and the information is also					
updated in t	he PSF thus the find	ing has been c	losed.		

CAR ID	01	Section no.	NA	Date: 03/06/2023
Description	of CAR			
PO has use	ed the GCC PSF terr	nplate version3	.2. PO is reque	sted to revise the PSF with reference
to the latest	available template v	ersion 4.0		
Project Ow	ner's response			Date: 07/07/2023
	s been revised to ve	rsion 4.0		
	tion provided by P			
Revised PS				
GCC Projec	t Verifier assessme	ent		Date: 24/08/2023
Project owne	er has revised the P	SF in the latest	template. Thus	s the finding has been closed.
CAR ID	02	Section no.	B.2	Date: 03/06/2023
Description	of CAR	•		
	the para 20 of GCC	PSF template	instructions,	
				has provided the justification for the
				per the para 5 and 6 of tool 07version
				the missing applicability condition
		5311 Y. FU 18 1	equest to duc	ι της πησοπης αρμησαυπης συπαπιοπ
justification.		where A and F		ion 10.0 is not provided in costics D.0
				ion 10.0 is not provided in section B.2
	is requested to provi			
			of Tool 27 version	on 11.0 is not provided in section B.2
of PSF. PP i	is requested to provi			
	s requested to provi	de the applicat	bility condition a	and its justification.
	· · ·	ide the applicat	bility condition a	and its justification.
Project Own	ner's response			Date: 07/07/2023
Project Owr The revised	ner's response PSF includes all the	applicability co		and its justification.
Project Owr The revised	ner's response	applicability co		Date: 07/07/2023
Project Own The revised Documenta	ner's response PSF includes all the tion provided by P	e applicability co roject Owner		Date: 07/07/2023 ol 07, Tool 21, and Tool 27.
Project Own The revised Documenta GCC Project	ner's response PSF includes all the tion provided by P et Verifier assessme	applicability co roject Owner ent	onditions for To	Date: 07/07/2023 ol 07, Tool 21, and Tool 27. Date: 24/08/2023
Project Own The revised Documenta GCC Project	ner's response PSF includes all the tion provided by P et Verifier assessme	applicability co roject Owner ent	onditions for To	Date: 07/07/2023 ol 07, Tool 21, and Tool 27.
Project Own The revised Documenta GCC Project Project owne	ner's response PSF includes all the tion provided by P at Verifier assessme er has added all the	applicability co roject Owner ent applicable tool:	onditions for To	Date: 07/07/2023 ol 07, Tool 21, and Tool 27. Date: 24/08/2023 us the finding has been closed.
Project Own The revised Documenta GCC Project Project owne CAR ID	ner's response PSF includes all the tion provided by P at Verifier assessme er has added all the 03	applicability co roject Owner ent	onditions for To	Date: 07/07/2023 ol 07, Tool 21, and Tool 27. Date: 24/08/2023
Project Own The revised Documenta GCC Project Project owne CAR ID Description	ner's response PSF includes all the tion provided by P of Verifier assessme er has added all the 03 of CAR	e applicability co roject Owner ent applicable tools Section no.	s in the PSF the	Date: 07/07/2023 ol 07, Tool 21, and Tool 27. Date: 24/08/2023 us the finding has been closed. Date: 03/06/2023
Project Own The revised Documenta GCC Project Project owne CAR ID Description It has been	ner's response PSF includes all the tion provided by P et Verifier assessme er has added all the 03 of CAR observed that PO 1	e applicability co roject Owner ent applicable tools Section no.	onditions for To s in the PSF thu B.4 Central Electrici	Date: 07/07/2023 ol 07, Tool 21, and Tool 27. Date: 24/08/2023 Us the finding has been closed. Date: 03/06/2023 ty Authority, CO2 baseline Database
Project Own The revised Documenta GCC Project Project owne CAR ID Description It has been version 17.0	ner's response PSF includes all the tion provided by P at Verifier assessme er has added all the 03 03 06 CAR observed that PO I 0 for obtaining the el	e applicability co roject Owner ent applicable tool: Section no.	s in the PSF the B.4 Central Electricito	Date: 07/07/2023 ol 07, Tool 21, and Tool 27. Date: 24/08/2023 us the finding has been closed. Date: 03/06/2023 ty Authority, CO2 baseline Database y system. However the latest version
Project Own The revised Documenta GCC Project Project owne CAR ID Description It has been version 17.0	ner's response PSF includes all the tion provided by P at Verifier assessme er has added all the 03 03 06 CAR observed that PO I 0 for obtaining the el	e applicability co roject Owner ent applicable tool: Section no.	s in the PSF the B.4 Central Electricito	Date: 07/07/2023 ol 07, Tool 21, and Tool 27. Date: 24/08/2023 Us the finding has been closed. Date: 03/06/2023 ty Authority, CO2 baseline Database
Project Own The revised Documenta GCC Project Project owne CAR ID Description It has been version 17.0 available is w	ner's response PSF includes all the tion provided by P et Verifier assessme er has added all the 03 of CAR observed that PO I of or obtaining the enversion 18.0. PO is r	e applicability co roject Owner ent applicable tools Section no.	onditions for To s in the PSF the B.4 Central Electricity of the electricity se the latest ver	Date: 07/07/2023 ol 07, Tool 21, and Tool 27. Date: 24/08/2023 Us the finding has been closed. Date: 03/06/2023 ty Authority, CO2 baseline Database / system. However the latest version sion and revise PSF accordingly. Date: 07/07/2023
Project Own The revised Documenta GCC Project Project owne CAR ID Description It has been version 17.0 available is the Project Own In the revised	ner's response PSF includes all the tion provided by P t Verifier assessme er has added all the 03 of CAR observed that PO I of obtaining the environment of the environment of problaming the environment of the environment of problaming the environment of the environment of the environment of problaming the environment of th	e applicability co roject Owner ent applicable tools Section no.	onditions for To s in the PSF the B.4 Central Electricity of the electricity se the latest ver	Date: 07/07/2023 ol 07, Tool 21, and Tool 27. Date: 24/08/2023 Us the finding has been closed. Date: 03/06/2023 ty Authority, CO2 baseline Database / system. However the latest version sion and revise PSF accordingly.
Project Own The revised Documenta GCC Project Project owne CAR ID Description It has been version 17.0 available is of Project Own In the revised CO ₂ baseling	ner's response PSF includes all the tion provided by P t Verifier assessme er has added all the 03 of CAR observed that PO I of obtaining the er version 18.0. PO is r ner's response d PSF, the Project O e Database.	e applicability co roject Owner ent applicable tools Section no. has used the C mission factor of requested to us	onditions for To s in the PSF the B.4 Central Electricity of the electricity se the latest ver	Date: 07/07/2023 ol 07, Tool 21, and Tool 27. Date: 24/08/2023 Us the finding has been closed. Date: 03/06/2023 ty Authority, CO2 baseline Database / system. However the latest version sion and revise PSF accordingly. Date: 07/07/2023
Project Own The revised Documenta GCC Project Project owne CAR ID Description It has been version 17.0 available is of Project Own In the revised CO ₂ baseling	ner's response PSF includes all the tion provided by P t Verifier assessme er has added all the 03 of CAR observed that PO I of obtaining the environment of the environment of problaming the environment of the environment of problaming the environment of the environment of the environment of problaming the environment of th	e applicability co roject Owner ent applicable tools Section no. has used the C mission factor of requested to us	onditions for To s in the PSF the B.4 Central Electricity of the electricity se the latest ver	Date: 07/07/2023 ol 07, Tool 21, and Tool 27. Date: 24/08/2023 Us the finding has been closed. Date: 03/06/2023 ty Authority, CO2 baseline Database / system. However the latest version sion and revise PSF accordingly. Date: 07/07/2023
Project Own The revised Documenta GCC Project Project owne CAR ID Description It has been version 17.0 available is of Project Own In the revised CO ₂ baseline Documenta	ner's response PSF includes all the tion provided by P at Verifier assessme er has added all the 03 of CAR observed that PO I of or obtaining the enversion 18.0. PO is r ner's response d PSF, the Project O e Database. tion provided by P	e applicability co roject Owner ent applicable tools Section no. has used the C mission factor of requested to us wners have util roject Owner	onditions for To s in the PSF the B.4 Central Electricity of the electricity se the latest ver	Date: 07/07/2023 ol 07, Tool 21, and Tool 27. Date: 24/08/2023 us the finding has been closed. Date: 03/06/2023 ty Authority, CO2 baseline Database y system. However the latest version sion and revise PSF accordingly. Date: 07/07/2023 .0 of the Central Electricity Authority's
Project Own The revised Documenta GCC Project Project owne CAR ID Description It has been version 17.0 available is v Project Own In the revised CO ₂ baseline Documenta	ner's response PSF includes all the tion provided by P at Verifier assessme er has added all the 03 of CAR observed that PO I of obtaining the environment version 18.0. PO is r ner's response d PSF, the Project O e Database. tion provided by P	e applicability co roject Owner ent applicable tools Section no. has used the C mission factor of requested to us wners have util roject Owner ent	onditions for To s in the PSF the B.4 Central Electricity of the electricity se the latest ver	Date: 07/07/2023 ol 07, Tool 21, and Tool 27. Date: 24/08/2023 us the finding has been closed. Date: 03/06/2023 ty Authority, CO2 baseline Database / system. However the latest version sion and revise PSF accordingly. Date: 07/07/2023 .0 of the Central Electricity Authority's Date: 24/08/2023
Project Own The revised Documenta GCC Project Project owne CAR ID Description It has been version 17.0 available is of Project Own In the revised CO ₂ baseline Documenta	ner's response PSF includes all the tion provided by P at Verifier assessme er has added all the 03 of CAR observed that PO I of obtaining the environment version 18.0. PO is r ner's response d PSF, the Project O e Database. tion provided by P	e applicability co roject Owner ent applicable tools Section no. has used the C mission factor of requested to us wners have util roject Owner SF with the late	onditions for To s in the PSF the B.4 Central Electricity of the electricity se the latest ver lized version 18	Date: 07/07/2023 ol 07, Tool 21, and Tool 27. Date: 24/08/2023 us the finding has been closed. Date: 03/06/2023 ty Authority, CO2 baseline Database y system. However the latest version sion and revise PSF accordingly. Date: 07/07/2023 .0 of the Central Electricity Authority's

	CAR ID	04	Section no.	B.4	Date: 03/06/2023
Project owner is requested to provide the justification for the applicability of the Simple OM method (with demonstration of the calculation as per the equations provided) as per the para 40 (a) and 4 (b) of tool 07, version 07. Moreover, it has been observed that PP has not provided the method for calculation of simple O as per the para 47 of Tool 07 version 07. PO is requested to provide the details on which options a per para 47 (a) and 47 (b) have been chose to calculate the Simple OM, with reference to the source provided as footnote (exact sheet name and cell number of CEA database). Also, in step 5 (Calculate the build margin (BM) emission factor), PO has chosen option 1 to calculate the build margin emission factor, but PO has not provided any details used for the calculation Therefore, PO is requested to demonstrate under the step on how the compliance with para 75 79 of Tool 07 version 07 has been met with references added in the footnote. Project Owner's response Date: 07/07/2023 In section B.4 of PSF, all the steps utilized to calculate Operating Margin (OM) and Build Marg (BM) have been explicitly outlined. These steps align with the methodology presented in Tool 0 version 07.0. Documentation provided by Project Owner Date: 24/08/2023 Project Verifier assessment Date: 24/08/2023 Project owner has revised the PSF with all the steps utilized to calculate Operating Margin (OM) ar Build Margin (BM) have been explicitly outlined. These steps align with the methodology presented	Descriptio	n of CL			
Project Owner's responseDate: 07/07/2023In section B.4 of PSF, all the steps utilized to calculate Operating Margin (OM) and Build Marg (BM) have been explicitly outlined. These steps align with the methodology presented in Tool 0 version 07.0.OmegaDocumentation provided by Project OwnerDate: 24/08/2023Project Verifier assessmentDate: 24/08/2023Project owner has revised the PSF with all the steps utilized to calculate Operating Margin (OM) and Build Margin (BM) have been explicitly outlined. These steps align with the methodology presented	In the sect Project own (with demo (b) of tool 0 Moreover, as per the p per para 47 provided as Also, in step the build n Therefore,	tion B.4 of PSF, unden ner is requested to p Instration of the calcu D7, version 07. it has been observed bara 47 of Tool 07 ve 7 (a) and 47 (b) have s footnote (exact she p 5 (Calculate the bun nargin emission fact PO is requested to o	rovide the justif ulation as per the ersion 07. PO is been chose to o et name and ce ild margin (BM) or, but PO has demonstrate un	ication for the applicability of the equations provided) as p ot provided the method for requested to provide the do calculate the Simple OM, wi fell number of CEA database emission factor), PO has ch is not provided any details der the step on how the co	of the Simple OM method ber the para 40 (a) and 40 calculation of simple OM etails on which options as th reference to the source b). Hosen option 1 to calculate used for the calculation. In public compliance with para 75 to
In section B.4 of PSF, all the steps utilized to calculate Operating Margin (OM) and Build Marg (BM) have been explicitly outlined. These steps align with the methodology presented in Tool O version 07.0. Documentation provided by Project Owner GCC Project Verifier assessment Project owner has revised the PSF with all the steps utilized to calculate Operating Margin (OM) ar Build Margin (BM) have been explicitly outlined. These steps align with the methodology presented			en met with ref	erences added in the footne	
Documentation provided by Project Owner GCC Project Verifier assessment Date: 24/08/2023 Project owner has revised the PSF with all the steps utilized to calculate Operating Margin (OM) ar Build Margin (BM) have been explicitly outlined. These steps align with the methodology presented	In section I (BM) have	B.4 of PSF, all the s been explicitly outlin			n (OM) and Build Margin
GCC Project Verifier assessment Date: 24/08/2023 Project owner has revised the PSF with all the steps utilized to calculate Operating Margin (OM) ar Build Margin (BM) have been explicitly outlined. These steps align with the methodology presenter			Project Owner		
Project owner has revised the PSF with all the steps utilized to calculate Operating Margin (OM) ar Build Margin (BM) have been explicitly outlined. These steps align with the methodology presenter	Document		Toject Owner		
Project owner has revised the PSF with all the steps utilized to calculate Operating Margin (OM) ar Build Margin (BM) have been explicitly outlined. These steps align with the methodology presenter	GCC Proje	ect Verifier assessm	ent		Date: 24/08/2023
	Project owner has revised the PSF with all the steps utilized to calculate Operating Margin (OM) and Build Margin (BM) have been explicitly outlined. These steps align with the methodology presented				

CAR ID	05	Section no.	B.5	Date: 03/06/2023
Description	of CL			
Project own	ner is requested to	comply to the	requirements of paragraph	h 10 and 28 of the CDM
			ysis, applied for the project	
It has been	observed that in se	ction B.5 of PS	SF, PO has demonstrated i	nvestment analysis using
			as not provided the date of i	
PSF and its	proof. Referring to a	the para 10 of [·]	Tool 27, PO is requested to	provide the evidence for
investment of	decision date and m	ention the sam	e in the PSF.	
Moreover, F	O has not mentione	d whether the f	inancial indicator used for in	nvestment analysis is pre-
tax or post t	ax equity IRR. PO is	requested to r	nention the same.	
Also, PO to	clarify Why land cos	t is not conside	ered in final year cash inflow	v as per "CDM Tool 27"
Project Ow	ner's response			Date: 07/07/2023
In the revise	ed version of the PS	F, the specific	dates of investment decision	ons made by both project
owners have	e been included. Ad	ditionally, the in	nvestment decision docume	ents have been furnished
and shared	with the verifier.			
For investme	ent analysis, the fina	ancial indicator	utilized is the post-tax equi	ty Internal Rate of Return
(IRR), as cle	(IRR), as clearly stated in the PSF.			
Regarding t	Regarding the financials, we would like to draw your attention to the Profit and Loss (P&L) sheet,			
where the sa	where the salvage value has been duly considered in the final year's cash inflow calculations.			
Documentation provided by Project Owner				
GCC Projec	t Verifier assessm	ent		Date: 24/08/2023

Project owner has specifically mention the investment decision date of the project along with the providing all the reference documents for the same. Also project owner has mentioned the the financial indicator utilized is the post-tax equity Internal Rate of Return (IRR), as clearly stated in the PSF.

Moreover the salvage value has been duly considered in the final year's cash inflow calculations in the Profit and loss sheet.

CAR ID	06	Section no.	3.5	Date: 03/06/2023
Descriptio	n of CAR			
In section i in the coun Project star The scope regulations, 1. Wind pow Pradesh, no 2. Madhya 3. MPERC 4. Indian el 5. Central e 6. Wind Da 7. Amendm 8. National	B.5 of PSF, PC try and state a ndard version 3 of legal requi , but not limited wer project poli otification date Pradesh Elect Electricity act a electricity grid co electricity author ta Sharing Pol pent in national Wind Solar Hy	nd demonstrate that the 3.1 para 46. irement test should be d to. icy, 2012 (New and rene d 30/01/2012 ricity Regulatory Comm 2003 ode regulations, 2010 ority (Installation and op icy -NIWE, 2019 I Wind-Solar Hybrid Poli vbrid Policy, 2018	e legal requiren demonstrated ewable energy o ission regulatio peration of mete icy, 2018	
9. Policy for	r repowering o	f the Wind Power Proje	cts, 2016	
	ment (Protecti /ner's respon			Date: 07/07/2023
In section E rules and re requiremen The list incl	3.5 of the PSF egulations app ts as per the 0 udes the name	, the Project Owner has licable in the country a GCC Project Standard v	nd state to dem ersion 3.1 para laws, acts, and	mprehensive list of all the relevant nonstrate compliance with the lega graph 46. regulations that the project activity
		d by Project Owner	<u> </u>	
	ct Verifier ass			Date: 24/08/2023
comprehend demonstration paragraph 4 The list incl	sive list of all e compliance 46. udes the name ensuring that	the relevant rules and with the legal requireme es of all the mandatory	regulations app ents as per the laws, acts, and	e Project Owner has provided a blicable in the country and state to GCC Project Standard version 3.1 regulations that the project activity and obligations and thus the finding

Description of CL It has been observed that PO has provided the sensitivity analysis of the project in the section B.5 of the PSF, However referring to para 28 of Tool 27 ,version 11, PO is requested to demonstrate the possible scenarios where the variations in the input parameter would breach the benchmark.

Section no. | B.5

07

CAR ID

Date: 03/06/2023

Project Owner's response

In section B.5 of the PSF, the Project Owners have provided a comprehensive analysis of all possible scenarios where variations in the input parameters would breach the benchmark values. **Documentation provided by Project Owner**

GCC Project Verifier assessment

VVB has cross checked that in section B.5 of the PSF, the Project Owners have provided a comprehensive analysis of all possible scenarios where variations in the input parameters would breach the benchmark values. Thus the finding has been closed

CAR ID08Description of CAR

In section B.71, data and parameter table "EG PJ, y (SDG -7)", PO has not provided the details of the electricity meters and their calibration dates. Since the project activity has already been started since 2016, PO is requested to provide this information in the data and parameter table.

Section no. | B.7.1

Moreover, estimated annual electricity generation is given as 16,031 MWh and its source is not provided, PO is requested to add the source of value as a footnote in the PSF.

Also, in the QA/QC column, PO has mentioned that "In absence or delay in the meter calibration. appropriate Guidelines will be applied appropriately to confirm the conservativeness of metering". PO has not clearly mentioned which guideline will be applied, and therefore is requested to provide the exact guideline to be applied in such situation.

Project Owner's response

In section B.7.1 of PSF, the Project Owner has included the specific details related to the electricity meters and their calibration dates.

Additionally, the PO has mentioned in a footnote within the PSF the source of the estimated annual electricity generation value, which is recorded as 16,031 MWh.

In cases where meter calibration is absent or delayed, the project will apply the guidelines issued by the CDM Executive Board (CDM EB) meeting 52, Annex 60, in the emission reduction calculations. **Documentation provided by Project Owner**

GCC Project Verifier assessment

Based on the response provided by the project owner above the requirements has been covered in the PSF with respect to the raised finding.

CAR ID	09	Section no.	B.7.1	Date: 03/06/2023
Descriptio	n of CAR			
			ble EGPJ,Y (SDG-7), PO	
	procedures. However, the QA/ QC procedures provided in the para 6.5, 6.6, 6.7, 6.8,6.9, 6.10, and			
	6.11 of Article 6, PPA has not been provided. PO is requested to revise the same to provide			
	Project Owner's responseDate: 07/07/2023			
				Date: 07/07/2023
	The monitoring plan's QA/QC procedure has been revised to align with the specific requirements mentioned in the Power Purchase Agreement (PPA).			
mentioned	in the Power Purchas	se Agreement (PPA).	

Documentation provided by Project Owner

Date: 07/07/2023

Date: 24/08/2023

Date: 03/06/2023

Date: 07/07/2023

Date: 24/08/2023

n closed

GCC Project Verifier assessmentDate: 24/08/2023Project owner has revised the section B.7.1 in the PSF to align the QA/ QC procedures provided in
the para 6.5, 6.6, 6.7, 6.8,6.9, 6.10, and 6.11 of Article 6, PPA.Date: 24/08/2023

Thus the finding has been closed.

Table 3. FARs from this Project Verification

FAR ID	01	Section no.	D.13	Date: 03/06/2023
Description	n of FAR			
The ER Ver	ifier should certify COF	RSIA Label (C+)	till 31 Dec 2020. Once the Ho	st Country Authorization
is provided	later, this can be verifie	ed in first or subs	sequent verifications.	
Project Ow	ner's response			Date: DD/MM/YYYY
Documenta	Documentation provided by Project Owner			
GCC Project Verifier assessment Date: DD/MM/YY			Date: DD/MM/YYYY	

DOCUMENT HISTORY

Version	Date	Comment
V 3.1	31/12/2020	 The name of GCC Program's emission units has been changed from "Approved Carbon Reductions" or ACRs to "Approved Carbon Credits" or ACCs.
V 3.0	23/08/2020	 Revised version released on approval by the Steering Committee as per the GCC Program Process; Revised version contains the following changes: Change of name from Global Carbon Trust (GCT) to Global Carbon Council (GCC); Considered and addressed comments raised by the Steering Committee: during physical meeting (SCM 01, dated 29 Oct 2019, Doha Qatar); and electronic consultations EC01-Round 04 (17.08.2020 – 22.08.2020).

		Feedback from the Technical Advisory Board (TAB) of ICAO on GCC submissions for approval under CORSIA ¹² ;
V 2.0	25/06/2019	Revised version released for approval by the GCC Steering Committee. This version contains details and information to be provided, consequent to the latest worldwide developments (e.g., CORSIA EUC).
v1.0	01/11/2016	Initial version released for approval by the GCC Steering Committee under GCC Program Version 1

¹²See ICAO recommendation for conditional approval of GCC at <u>https://www.icao.int/environmental-protection/CORSIA/Documents/TAB/Excerpt_TAB_Report_Jan_2020_final.pdf</u>



www.globalcarboncouncil.com